


APPENDIX C



**A STREAM RESTORATION PLAN
FOR A PROPOSED SURFACE MINE
NEAR SUGAR BRANCH,
KNOTT COUNTY, KENTUCKY
(APPLICATION No. 860-0380, A. No. 6)**

Prepared for:
Logos Engineering, Inc.
Manchester, Kentucky
&
Nally & Hamilton Enterprises, Inc.
Bardstown, Kentucky

Prepared by:
Joel Beverly

Apogee Environmental Consultants, Inc.

P.O. Box 338
Ermine, KY 41815
PHONE: (606) 633-7677
FAX: (606) 632-2626

Apogee Project # 05-104.00

March 2006



Letter of Transmittal

Attention:
Mr. Darwin Messer
USACE
845 Sassafras Creek Road
Sassafras, KY 41759-8806

DATE	PROJECT #	DELIVERED VIA:	SUBMITTED BY:	RECEIVED BY:
7/12/06	05-104.00	Hand	Joel Beverly	

QTY.	DESCRIPTION
6	A STREAM RESTORATION PLAN FOR A PROPOSED SURFACE MINE NEAR SUGAR BRANCH, KNOTT COUNTY, KENTUCKY (APPLICATION No. 860-0380, A. No. 6)

Dear Mr. Messer,

Please find enclosed a stream restoration plan for a proposed surface mine near Redfox, Knott County, Kentucky (Application No. 860-0380, A. No.1). The applicant (Nally & Hamilton Enterprises, Inc.) requests that this plan be considered by the USACE for a Nationwide 21 Permit. If you should have any questions or comments concerning this project, please feel free to contact me at my office.

Sincerely,

A handwritten signature in black ink, appearing to read "Joel Beverly".

Joel Beverly
Director of Environmental Services

CC: Mr. Rusty Roberts, Logos Engineering, Inc. (Letter of Transmittal)
Mr. Les Williams, Nally & Hamilton Enterprises, Inc. (1 copy)
File (1 copy)

TABLE OF CONTENTS

	<u>Page</u>
TABLE OF CONTENTS.....	2
LIST OF TABLES	3
LIST OF FIGURES.....	4
1.0 INTRODUCTION.....	5
2.0 SITE LOCATION AND DESCRIPTION.....	5
2.1 Direct and Indirect Impacts.....	5
2.2 Physiography	10
2.3 Purpose of Project.....	10
2.3.1 Method of Operation.....	10
2.3.2 Bench Pond Construction.....	11
2.3.3 Drainage Corridors.....	12
2.3.4 Best Management Practices	12
2.4 Project Timeline	12
3.0 SURVEYS CONDUCTED	12
3.1 Aquatic Biological Assessment	13
3.1.1 Habitat Assessment	13
3.1.2 Physiochemical	14
3.2 Physical Characteristics	14
4.0 IMPACTS TO STREAM	15
4.1 Alternatives Analysis	15
4.2 Stream Assessment	16
4.3 Cumulative Impacts Analysis	17
5.0 STREAM RESTORATION PLAN.....	17
5.1 Stream Habitat	18
5.2 Riparian Habitat	19
5.2.1 Grasses.....	20
5.2.2 Trees.....	20
6.0 MITIGATION	21
6.1 Mitigation Work Plan	21
6.2 Site Protection.....	22
7.0 MONITORING	25
7.1 Monitoring and Long-term Management	25
7.2 Financial Assurances	26
8.0 RESPONSIBLE PARTIES	27
8.1 Applicant	27
8.2 Preparer of Restoration Plan.....	27
9.0 LITERATURE CITED	28

LIST OF TABLES

<u>Table</u>	<u>Page</u>
Table 1. Vegetation analysis using DSMRE's Constructed Vegetative Stratum Rank System at three streams in Knott County, Kentucky (Permit No. 860-0380, A. No. 6).....	13
Table 2. Stream pattern, profile, and dimension data at unnamed tributary to Carr Creek Lake that will be used to guide restoration efforts at three streams in Knott County, Kentucky.	15
Table 3. Stream lengths, Ecological Integrity Index (EII), and Ecological Integrity Units (EIUs) at three streams in Knott County, Kentucky (Permit No. 860-0380, A. No. 6).....	16
Table 4. Seeding rates for grasses, legumes, and temporary plants at proposed permit area, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).	20
Table 5. Recommended tree species for revegetation of riparian areas, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).....	21
Table 6. Stream compensation ratio calculator for proposed mitigation efforts at three streams in Knott County, Kentucky (Permit No. 860-0380, A. No. 6).	23
Table 7. In-lieu fee summary at three streams in Knott County, Kentucky (Permit No. 860-0380, A. No. 6).	23
Table 8. Individual habitat assessment parameters for hollowfills No. 15, 16, and 17 and sediment structures No. 106, 107, and 92 for present day, immediately after restoration, and 30 years after restoration, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).	24
Table 9. Factors to be considered when determining successful stream restoration, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).	26

LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
Figure 1. Proposed permit boundary and stream areas to be impacted, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).....	6
Figure 2. Restored stream areas for mitigation at hollowfill No. 15 and sediment pond No. 106, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).	7
Figure 3. Restored stream areas for mitigation at hollowfill No. 16 and sediment pond No. 107, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).	8
Figure 4. Restored stream areas for mitigation at hollowfill No. 17 and sediment pond No. 92, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).	9

APPENDICES

- APPENDIX A:** Completed High Gradient Stream Data Sheets
- APPENDIX B:** Stratum Rank Key
- APPENDIX C:** Completed Data Sheets for Longitudinal Profiles, Pebble Counts, and Cross Sections
- APPENDIX D:** Longitudinal Profile, Cross Sections, and Pebble Counts for Streams to be Disturbed at Proposed Project
- APPENDIX E:** Longitudinal Profile, Cross Sections, and Pebble Counts for Five to Seven Percent Grade Stream
- APPENDIX F:** Stream Compensation Ratio Calculator Forms
- APPENDIX G:** EII Calculation Spreadsheets for Pre-disturbance
- APPENDIX H:** EII Calculation Five Years after Disturbance
- APPENDIX I:** EII Calculation for 30 Years after Disturbance

ATTACHMENTS

- ATTACHMENT 1:** J-hook Diagram
- ATTACHMENT 2:** Log Vane Diagram
- ATTACHMENT 3:** Rock Vane Diagram
- ATTACHMENT 4:** Step Pool Diagram

1.0 INTRODUCTION


Apogee Environmental Consultants (Apogee) was contracted by Logos Engineering, Inc. to prepare a post-mining stream restoration plan for three streams in Knott County, Kentucky. The proposed mine by Nally & Hamilton Enterprises, Inc. [Department of Natural Resources (DNR) Permit No. 860-0380, A. No. 6] and the associated streams to be disturbed are shown in Figure 1. This plan is hereby submitted to U. S. Army Corps of Engineers (USACE) on behalf of Logos Engineering, Inc. and Nally & Hamilton Enterprises, Inc to fulfill the requirements set forth by USACE concerning Section 404 of the Clean Water Act and Section 10 of the Rivers and Harbors Act of 1899.

2.0 SITE LOCATION AND DESCRIPTION

The project area is located in Knott County, Kentucky, approximately 1.0 miles southwest of the community of Redfox (Figure 1). The proposed permit area, which is situated on the ridges, slopes and hollows, between Sugar Branch and Defeated Creek, covers approximately 214.5 surface acres. There will be three hollow fills (hollowfills No. 15, 16, and 17) and three associated sediment control ponds (sediment ponds 106, 107, and 92) for the proposed permit that will impact waters of the United States. Hollowfill No. 15 and sediment control pond No. 106 are located in an Unnamed Tributary to Defeated Creek, Hollowfill No. 16 and sediment control pond No. 107 are located in the headwaters of Sugar Branch, and Hollowfill No. 17 and sediment control pond No. 92 are located in the headwaters of and unnamed tributary to Carr Creek Lake. Defeated Creek also flows into Carr Fork Lake while Sugar Branch flows into Breeding Creek. All three affected stream sections are small (1st order) and are located within the North Fork Kentucky River drainage system. All three affected stream sections have intermittent and ephemeral sections.

2.1 Direct and Indirect Impacts

Hollow fill No. 15 will impact 1,729 feet of stream while Sediment Structure No. 106 will impact 112 feet of stream. Hollow fill No. 16 will impact 1,839 feet of stream while Sediment Structure No. 107 will impact 135 feet of stream. Hollow fill No. 17 will impact 684 feet of stream while Sediment Structure No. 92 will impact 105 feet of stream. It is expected that approximately 0.53 acres of waters of the U.S. will be impacted during project operations. The drainage areas above



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.


P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2626
Email: jcalhoun@earthlink.net

**NALLY & HAMILTON
ENTERPRISES**

**Figure 1. Proposed Surface Mine,
Hollowfill, Pond, and
Biological Assessment Sites.**

SCALE: 1"=1000'

1/11/06



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.


P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41915 Fax: (606) 632-2626
a.thompson@hotmail.com

**NALLY & HAMILTON
ENTERPRISES, INC.**

Figure 2. Restored Stream Areas for Mitigation at Fill 107-A5, Sediment Pond 107-A5, and stream reach between them, Knott County, Kentucky.

SCALE: 1"=300'

11/15/05



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.


P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2626
Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
ENTERPRISES, INC.**

Figure 3. Restored Stream Areas for Mitigation at Fill 15-A5, Sediment Pond 106-A5, and stream reach between them, Knott County, Kentucky.

SCALE: 1"=300'

11/15/05



APOGEE
 ENVIRONMENTAL CONSULTANTS, INC.

P.O. Box 338 Tel: (606) 633-7877
 Ermine, KY 41815 Fax: (606) 632-2626
 Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
 ENTERPRISES, INC.**

Figure 4. Restored Stream Areas for Mitigation at Fill 17-A6, Sediment Pond 92-A6, and stream reach between them, Knott County, Kentucky.

SCALE: 1"=300'

1/11/06

the toe of hollowfills No. 15, 16, and 17 are 67, 64, and 33 acres respectively. The drainage areas above the dams of sediment structures No. 106, 107, and 92 are 69.8, 66.5, and 35.9 acres respectively. Approximately 1,245,596, 1,243,772, and 1,868,113 cubic yards of fill material will be placed into hollowfills No. 15, 16, and 17 respectively. There will be no impacts to wetlands during the proposed mine project. Direct impacts are illustrated in Figures 2, 3, and 4. No indirect impacts are planned for the project.

Features which might create adverse surface water conditions are existing roads, previous logging operations, existing gas wells, and previous mining operations. No other conditions are known to exist in the watershed which may create any adverse surface water conditions. With the exception the above disturbances, the drainages are completely forested. The proposed project area is located on the Blackey USGS quadrangle.

2.2 Physiography

The project area is situated in the Dissected Appalachian Plateau Ecoregion (Woods et al. 2002). The ecoregion is characterized by narrow ridges, deep coves, narrow valleys, and a mostly forested landscape. Forest types in this ecoregion consist of mixed mesophytic in coves and on north- and east-facing slopes, and mixed oak forests in more upland situations and south- and west-facing lower slopes. White oak forests are also common. Overall, forest composition is highly variable, influenced by such factors as aspect, previous land usage, and degree of slope and topographical shading. Many streams in this ecoregion are cool and high gradient; with a substrate commonly consisting of cobble and boulder (riffles are common). The underlying geology consists of Pennsylvanian shale, siltstone, sandstone, and coal. The presence of coal mining (and also logging and gas exploration) has led to many streams being degraded. Nutrient levels in streams are low, a result of the areas low population, limited farming, and non-carbonate rocks.

2.3 Purpose of Project

2.3.1 Method of Operation

This application proposes surface mining of the area shown on the attached maps. Mining is expected to begin within two months of the final issuance of the permit.

Removal of overburden and coal will be conducted by conventional surface mining methods. Equipment utilized will consist primarily of drills, dozers, loaders, and trucks. Drills (RDC-16) will assist in the blasting of material, with dozers (155 KOMATSU) and loaders (988 CAT) moving the overburden. Trucks (769 CAT) will be used if necessary to transport material to storage areas.

Initially, organic material will be removed before topsoil can be stockpiled. All trees and brush will be windrowed on the solid berm. Since small underbrush, weeds, grasses, and a few small trees are the only forms of organic matter present, non-woody organic matter may be mixed with overburden materials where no stability problems will be created.

All topsoil will be removed and stockpiled or immediately redistributed on a regarded area. Complete procedures for handling topsoil are described in the topsoil handling plan. If topsoil is not redistributed within thirty days, the stockpile will be seeded to prevent erosion, etc.

Once topsoil has been removed from a site, overburden removal will begin. As stated previously, loaders, trucks, and dozers will transport material from the coal removal pit. Coal will then be removed following overburden removal. Coal removal from each pit should not exceed two weeks under normal conditions. However, variables such as weather and equipment breakdowns may cause additional delays. In no case will the highwall created from each individual pit be left unreclaimed for more than 60 days from initial disturbance.

Backfilling will be an automatic process. After coal has been removed from the pit area, overburden from the next proposed coal extraction point will be transported to reclaim behind the preceding operation. This operation proposes to have multiple pits (5 maximum) open simultaneously to allow coal haulage on a continuous basis. However, no more than 1500' of total collective highwall will be exposed at any one time. This is necessary to fulfill contract obligations with the purchaser. However, coal removal in a given location shall be completed within sixty (60) calendar days after the initial surface disturbance at that location. Backfilling and grading to approximate original contour shall follow coal removal by not more than sixty (60) days and by not more than 1500 linear feet. Final grading will ensure that all highwalls are eliminated. The area will be compacted by several passes on each layer with the use of heavy equipment.

Following final grading of slopes, topsoil will be reapplied. Care will be taken to prevent compaction of this material. The area will then be seeded and mulched according to the revegetation plan. Any eroded gullies will be regraded, reseeded, and stabilized or rip-rapped.

2.3.2 Bench Pond Construction

Bench ponds will be constructed per enclosed designs at locations shown on the MRP map. However, bench ponds will not be constructed until mining has progressed through the pond location and any coal within the pond location is removed. Prior to pond construction, mining on the bench in a particular watershed will contain all the water in the pit until the pond area has been mined through and the pond constructed. Since the size of the pit will exceed the pond

size, water holding capacities will exceed those of the pond, thereby, providing adequate sediment control. In no case will runoff be allowed to leave the permitted area without first passing through a certified sediment facility. Bench ponds will be built on lowest coal seam to be mined.

2.3.3 Drainage Corridors

Drainage corridors will be permitted between the mining/storage area and the sediment pond proposed. As shown on the enlarged MRP map, the corridor will include the drainage channel and on area adjacent to the channel for access. Total width is proposed at 30 feet. This includes approximately 10 feet for the drainage channel and areas adjacent to it for any mitigation that might arise, and 20 feet to allow equipment access. However, damage to drainage ways is not expected if design plans within the application are followed.

2.3.4 Best Management Practices

This proposed operation intends to use the best management practices available to ensure protection of the lower lying streams and the associated areas. Erosion will be minimized by immediate seeding, mulching and revegetating of disturbed areas including ponds and outcrops. Hay checks will be placed in areas where erosion gullies or concentrated flows may occur. During pond construction, hay checks will be placed below the disturbance to filter initial disturbance runoff. Likewise, hay checks will be used if necessary along roadway ditches or any temporary ditches or drainage channels created. Rip-rap will be used when velocities or volume of runoff dictates. Throughout the mining process, care will be taken to minimize erosion and protect surface and groundwater quantity and quality. Measures will be taken, as conditions dictated, to prevent adverse effects to the area.

2.4 Project Timeline

Mining will begin immediately or very soon after approval is received from the USACE. The life of each mine permit will vary depending on the amount of coal that can be economically mined from each permit. Economic mineability will depend upon the sales price of coal and, thus, a definite length of mining is hard to define. Despite the unknowns, mining operations are expected to last for approximately 3 years.

3.0 SURVEYS CONDUCTED

Several site visits by personnel from Apogee have been made to determine the existing conditions at the three streams that will be impacted during mine operations. This information will guide restoration efforts and will be used to determine if these efforts are a success.

3.1 Aquatic Biological Assessment

The two unnamed tributaries were visited on 10 November 2005 to conduct an aquatic biological assessment. However, due to the streams flowing at such a low level, benthic sampling was not conducted.

3.1.1 Habitat Assessment

The method used to analyze habitat followed Rapid Bioassessment Protocols for use in Wadeable Streams and Rivers: Periphyton, Benthic Macroinvertebrates, and Fish (2nd Edition) (Barbour et al. 1999). Sample sites were visited on 2 and 14 December 2005 and 8 January 2006 by Apogee biologists, with stream conditions and riparian vegetation being recorded at each site. Stream conditions at each site were assessed using the High Gradient Stream Data Sheet (Barbour et al. 1999). The following stream condition parameters were assessed at each site: available cover, embeddedness, velocity/depth regime, sediment deposition, channel flow status, channel alteration, frequency of riffles (or bends), bank stability, vegetative protection, and riparian vegetative zone width. The completed data sheets for each site can be found in Appendix A. Riparian vegetation was analyzed using DSMRE's constructed vegetative stratum rank system (Appendix B). Results of the vegetation survey are shown in Table 1.

Table 1. Vegetation analysis using DSMRE's Constructed Vegetative Stratum Rank System at three streams in Knott County, Kentucky (Permit No. 860-0380, A. No. 6).

Common Name	Latin Name	HF #15 and SS #106	HF #16 and SS #107	HF #17 and SS #92
Tulip Tree	<i>Liriodendron tulipifera</i>	5	6	7
Eastern Hemlock	<i>Tsuga canadensis</i>	8		
Sycamore	<i>Platanus occidentalis</i>	5		1
Umbrella Magnolia	<i>Magnolia tripetala</i>	1	2	1
Sweet Birch	<i>Betula lenta</i>	2		2
Black Gum	<i>Nyssa sylvatica</i>	2	4	
Beech	<i>Fagus grandifolia</i>	4	6	5
Flowering Dogwood	<i>Cornus florida</i>	1		1
Basswood	<i>Tilia Americana</i>	1	1	2
Service Berry	<i>Amelanchier arborescens</i>	2		
Black Oak	<i>Quercus velutina</i>		7	
Sugar Maple	<i>Acer saccharum</i>		4	2
Red Maple	<i>Acer rubrum</i>		4	

Common Name	Latin Name	HF #15 and SS #106	HF #16 and SS #107	HF #17 and SS #92
Cucumber Tree	<i>Magnolia accuminata</i>		1	
Shagbark Hickory	<i>Carya ovata</i>		4	
Black Locust	<i>Robinia pseudoacacia</i>			1
Sourwood	<i>Oxydendron arboreum</i>			2
Yellow Buckeye	<i>Aesculus flavus</i>			3
Spice Bush	<i>Lindera benzoin</i>			1
Hydrangea	<i>Hydrangea arborescens</i>			1

3.1.2 Physiochemical

Measurements were taken for specific conductance during the 2 and 14 December 2005 and 8 January 2006 site visits. Conductivity levels for hollowfills No. 15, 16, and 17 were 410, 270, and 368 respectively.

3.2 Physical Characteristics

Based upon Rosgren's (1994) classification system, stream sections at hollowfills 15, 16, and 17 are considered A3a+, while the stream sections at sediment structure 106, 107, and 92 are considered A3. Both stream types are characterized by having high entrenchment, high gradient (>10 % slope for A3a+ streams and between 4 and 10 % slope for A3 streams), low sinuosity, and a substrate consisting mostly of cobble. The areas of stream to be impacted were assessed using the High Gradient Stream Data Sheet. The streams were in poor condition and thus scored very low (Appendix A). Based upon the streams being in such poor condition, a stream of similar size, but in better condition, was surveyed to get stream pattern, profile, and dimensions to help guide stream restoration efforts. The results of this assessment are located in Table 2. The completed data sheets for longitudinal profiles, pebble counts, and cross sections are located in Appendix C. Longitudinal profiles, cross sections, and pebble counts were also surveyed at all proposed disturbed streams to show current conditions (Appendix D).

Table 2. Stream pattern, profile, and dimension data at unnamed tributary to Carr Creek Lake that will be used to guide restoration efforts at three streams in Knott County, Kentucky.

Characteristic	Score	
	HF Areas	Pond Areas
Pattern		
Sinuosity	1.22	1.17
Profile		
Slope	20.9	10.2
Dimension		
Bankful Width (ft)	5.9	8.0
Mean Depth (ft)	Dry	.3
Maximum Depth (ft)	Dry	1.8
Bankful Depth (ft)	1.5	.85
Width/depth Ratio	3.9	9.4
Floodprone width (ft)	9.3	12.6
Entrenchment Ratio	1.6	1.6

4.0 IMPACTS TO STREAM

4.1 Alternatives Analysis

To ensure that as little stream as possible is impacted, a number of changes have been made to the original engineering plans. Plans had originally called for the construction of sediment ponds farther downstream from each hollowfill. However, after discussing these plans, the client decided to move the sediment control structures as close as practical to the toe of the hollow fills.

To completely ensure that the client is taking the appropriate action concerning waters of the U.S., other options were also considered. Using deep mines instead of area and auger mining techniques were considered. However, deep mining would result in limited resource recovery and would not discourage potential future mining in the same area. Also, due to the area being previously affected by pre-law mining, current proposed activities will remove high wall areas and restore the topography to a more natural slope.

Other options considered included the possibility of using upland areas for the storage of waste materials and also using only two hollowfills. However, both of these alternatives were not viable due to the amount of excess material to be disposed of. Due to the large amount of waste material, it is not practical to

place this material in upland areas. Optimally, this amount of fill could be placed in two hollowfills, however, if only two hollowfill were used, this would lead to more fill being placed into intermittent streams than is proposed in the current work plan. In addition, the three streams that will have hollowfills located in them have been heavily disturbed by past mining. Based upon this, it was not thought that using these streams would greatly impact overall water quality in the area.

Therefore, three hollowfills are proposed, one each on the three stream sections to be disturbed during mining activities. Neither of the streams to be impacted is considered to be a high quality stream, as indicated by the above surveys conducted. Before disturbance is to begin upstream, Ponds 106, 107, and 92 will be constructed to provide sediment control measures for each of the drainages.

4.2 Stream Assessment

The streams were assessed using the Ecological Integrity Index (EII) and Ecological Integrity Units (EIUs) developed by USACE (Table 3). EII is measured as quality per running foot and is scored from 0 – 1 (with 1 being equal to least disturbed conditions in the region). Ecological Integrity Units are calculated by multiplying the EII by length of stream to be impacted (in feet) (Table 1).

Table 3. Stream lengths, Ecological Integrity Index (EII), and Ecological Integrity Units (EIUs) at three streams in Knott County, Kentucky (Permit No. 860-0380, A. No. 6).

Impact Reach Name	Stream Length (ft)	EII	EIU
Hollowfill #15 (ephemeral)	665	.20	133
Hollowfill #15 (intermittent)	1,064	.20	212.8
SS #106 (intermittent)	112	.20	22.4
Hollowfill #16 (ephemeral)	814	.38	309.3
Hollowfill #16 (intermittent)	1,025	.38	389.5
SS #107 (intermittent)	135	.39	52.7
Hollowfill #17 (ephemeral)	684	.25	171
SS #92 (intermittent)	105	.25	26.3
Total	4,604		1,317

4.3 Cumulative Impacts Analysis

In addition to the proposed direct affects on the streams, the incremental impact of the proposed activities when added to other past, present and reasonably foreseeable future actions were also taken into account. Future land disturbances that could potentially occur in the drainages include logging operations and powerline corridor development. It is unlikely that there will be any agricultural development or road construction, due to the hollows being so small, steep, and remote. It is also unlikely that additional mining activities will occur in the drainage after current proposed activities are concluded.

In addition to the above potential future land disturbance activities, there will also be some watershed improvement projects. The proposed streams that will be affected during this project have been heavily impacted by past mining. Past mining areas that are located below the toe of the proposed hollowfills will be restored as closely as possible to a healthy stream system. In addition to the stream sections below the toe of the hollow fill, natural stream sections will also be constructed on both sides of each hollowfill.

5.0 STREAM RESTORATION PLAN

Once all mining activities are completed, the streams will be restored as closely as possible to a healthy stream system. All three streams to be impacted are of very low quality, and thus are not a good guide to restoring the streams. Therefore, a similar size, higher quality stream was surveyed. The results of this survey will guide restoration efforts.

The purpose of this restoration plan is to return stability and ecological function to the impacted streams, while also making the streams self-maintaining. The pattern, profile, and dimension data collected at the high quality stream site will be used to guide the stream restoration efforts. Restoration measures to be employed include stream shaping and realignment, revetments (riffles, boulder clusters; substrate, cover logs, J-hook vanes, and cross vanes), and bioengineering (revegetation).

All sediment control ponds will be removed and each stream restored to a self-maintaining system, while hollowfills will have natural channels constructed on the sides of each (Figures 2, 3, and 4). During the removal of the sediment control ponds, silt fences and/or rows of straw will be employed to reduce the amounts of sediment that will impact the downstream areas. All stream restoration efforts will be conducted during low flow situations.

5.1 Stream Habitat

Current in-stream habitat is not in a natural, self-maintaining condition. All three streams have been impacted by previous mining and logging operations. The streams at proposed hollowfills No. 15 and 17 have old sediment control structures located in them (proposed sediment control structures will be located in the same spot as existing sediment structures) while the stream at proposed hollowfill No. 16 has been heavily affected by logging. Due to these disturbances, we surveyed a more natural, similar size stream located off-site to guide restoration efforts.

During restoration efforts, in-stream habitat will be re-created as closely as possible to a natural stream channel (following data collected at the off-site stream). This will include reproducing as closely as possible the bankfull width, depth, channel sinuosity, riffle-run-pool ratio, and substrate types. The longitudinal profile (riffle/run/pool), cross sections, and pebble count data collected will be used to guide restoration efforts. A diverse in stream habitat will be achieved by using rock/log deflectors, riffles, boulder clusters, substrate (cobble and gravel), cover logs, J-hook vanes (made of large rock, logs, and/or root wads), and cross vanes (rock and log). These structures will help make the stream self-maintaining and also provide a diverse habitat for aquatic organisms. During the construction phase, data sheets detailing current conditions should be referred to to ensure that restoration efforts are being created as closely as possible to pre-disturbance conditions.

In stream restoration structures will be placed in such a way to create a self-maintaining stream. Where bends in the stream are proposed, J-hook vanes will be placed to stabilize the banks and to form a scour pool in the center portion of the channel (Attachment 1). Placing the J-hook vanes in the stream bends will help dissipate energy during high flow situations. The vane arm sections of the J-hook vanes (near the bank) will be interlocked with no spaces in between, thus stabilizing the banks as much as possible. These structures should be built at a 20 to 30 degree angle from the bank. The center sections of the J-hook vanes (that jut out into the middle of the stream) will have gaps located in between the large rocks. These gaps will help transport sediment and improve channel capacity and sediment competence. The vane arm section of the J-hook should be one-third the bankfull width of the stream channel and the center section should cover another one-third. Footers for these structures should be three times the protrusion height of the invert rock.

Where sections of the stream are currently straight, cross-vanes will be placed to help provide pool/run habitat. These structures will decrease stream velocity and power near the bank and increase it near the center. Cross vanes will be constructed of either logs or boulders (Attachment 2 and 3). Logs used for these cross vanes will have a 12 to 18 inch diameter and will be at least 18 feet long.

To ensure that the logs will not be washed out during high flow situations, log ends will be buried at least two feet within each bank. Cross vanes constructed of boulders will have footers that are three times the protrusion height of the invert rock. The arm vane arm structures should be built at a 20 to 30 degree angle from the bank. Bankfull levels will be approximately six inches above cross vane structures. These structures will be constructed approximately five to seven bankfull widths of each other.

In areas that are currently occupied by step pools, interlocking cross-vanes will be placed to mimic as closely as possible the pre-disturbance conditions (Attachment 4). These structures will also help dissipate energy during high flow situations and will provide small pockets of deep water habitat for aquatic organisms.

In addition to the stream sections below the toe of the hollow fill, natural stream sections will also be constructed on both sides of each hollowfill. The sides of these drainages will be rip-rapped while the inside sections will have a natural stream channel design. Although there will be drainages down both sides of the hollowfills, the flow of water will be concentrated into only one of these stream sections as to ensure the highest water flow throughout the year. These restored sections will be constructed on solid ground near where the hollow fill comes in contact with the natural terrain. This will help ensure that water does not sink into the fill area but instead flows above ground. In addition, the tree line should come very close to the side of each hollow fill and help to create a more natural setting more quickly. Cross-vanes (made of logs) will be placed in these sections of restored stream to help provide pool/run habitat and to help create a system that is self-maintaining.

In addition to the above listed restoration methods, the restoration will utilize small boulders, cobble, and gravel to mimic as closely as possible the current conditions of the healthy stream. These will help give the stream a natural look and will provide habitat for aquatic organisms. Rock used for the restoration efforts will be a durable sandstone obtained on-site during project operations.

5.2 Riparian Habitat

Once the stream restoration efforts are complete, the riparian vegetation will be re-established. This riparian vegetation will help prevent sedimentation of the streams, keep water temperatures cool (by shading), and provide nutrients for organisms that live within the stream. Mesic-hydric and hydric shrubs will be planted between the normal flow and bankfull areas. This riparian zone will be 60 feet wide on both sides of the stream. During the revegetation process, the site will have hydromulch applied. The hydromulch will aid in the retention of water and help prevent the site from becoming excessively dry. As this mulch decays it will also build additional topsoil.

5.2.1 Grasses

The site will be seeded with temporary groundcover, legumes and permanent grass. The temporary plants to be seeded will include either foxtail millet (*Setaria italica*), annual rye (*Lolium multiflorum*), or winter cereal rye (*Secale cereale*). To insure seeding and to diversify the temporary vegetation, a combination of these species may be used. During seeding a species of legume [white clover (*Trifolium repens*)] will be selected to achieve nitrogen fixation in the soil and to provide quick growing ground cover. In addition to temporary plants and legumes, two species of permanent grasses will be seeded to help build topsoil and to provide quick soil cover. The grasses to be seeded will be a combination of little blue stem (*Schizachyrium scoparium*); redtop (*Agrostis alba*), and little blue stem; or orchard grass, redtop, and little blue stem. See Table 4 for seeding rates for the grasses, legumes, and temporary plants.

Table 4. Seeding rates for grasses, legumes, and temporary plants at proposed permit area, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).

Types of Plants and Common Name	Rate per Acre
Permanent Grass	
Redtop Grass	3 lbs
Little Blue Stem	3 lbs
Legume	
White clover	3-5 lbs
Temporary Plants	
Foxtail Millet	5-10 lbs
Annual Rye	15-20 lbs
Winter Cereal Rye	15-20 lbs

5.2.2 Trees

Native species of trees that are currently known from the site should be used whenever they are available from the Kentucky Division of Forestry and Nurseries. The exact species of trees to be used will be determined at a later time and will depend on availability. However, at least three species each of trees and shrubs should be used to revegetate the riparian areas. A total of 500 stems per acre will be planted as part of the revegetation plan (350 trees and 150 shrubs). Revegetation will be considered a success if after five years there are 300 stems per acre of live trees and shrubs (200 trees and 100 shrubs). Both trees and shrubs should be planted between three and six feet from each other. This will help ensure that enough vegetation is planted to get the benefits of the riparian habitat, without the vegetation being too densely packed. Trees planted will be bare root stock. In addition to planted species, the site will probably have some native volunteer species invade. Table 5 lists recommended tree species for revegetation of the riparian areas.

Table 5. Recommended tree species for revegetation of riparian areas, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).

Common Name	Scientific Name	Hydrologic Regime
Tree Species		
Silver Maple	<i>Acer saccharinum</i>	Mesic
Sugar Maple*	<i>Acer saccharum</i>	Intermediate Mesi/Xeric
Yellow Birch	<i>Betula alleghaniensis</i>	Mesic
Sweet Birch*	<i>Betula lenta</i>	Mesic
Tulip Tree*	<i>Liriodendron tulipifera</i>	Mesic
Sweet Gum	<i>Liquidambar styraciflua</i>	Hydric
Sycamore*	<i>Platanus occidentalis</i>	Mesic-Hydric
Basswood*	<i>Tilia americana</i>	Mesic
Northern Red Oak	<i>Quercus rubra</i>	Mesic
American Elm	<i>Ulmus americana</i>	Mesic-Hydric
Red Elm	<i>Ulmus rubra</i>	Mesic-Hydric
Eastern Hemlock*	<i>Tsuga canadensis</i>	Mesic
Shrub Species		
Alder	<i>Alnus serrulata</i>	Hydric
Black Willow*	<i>Salix nigra</i>	Hydric
Elderberry	<i>Sambucus Canadensis</i>	Mesic-Hydric
Ironwood	<i>Carpinus caroliniana</i>	Mesic-Hydric
Maple-leaved Viburnum	<i>Viburnum acerfolia</i>	Mesic
Witch Hazel	<i>Hamamelis virginiana</i>	Mesic
Hydrangea *	<i>Hydrangea arborescens</i>	Mesic-Hydric
Spicebush*	<i>Lindera benzoin</i>	Mesic

- * = Tree and shrub species that are currently growing on the permit area.

6.0 MITIGATION

Under existing law the USACE requires compensatory mitigation to replace aquatic resource functions unavoidably lost or adversely affected by authorized activities. The objective of this mitigation plan is to compensate for adverse conditions associated with the loss of 4,604 feet of stream. To compensate the client will do on-site mitigation and also pay an in-lieu-fee.

6.1 Mitigation Work Plan

Mitigation for the sediment structures will be conducted within the degraded streambeds, while mitigation for the the hollowfills will be conducted by constructing natural stream drainages on the sides. Linear feet restored for the

ponds will be equal to pre-disturbance levels. There will be one drainage at the top of each hollowfill and one drainage down each side. Figures 2-4 and Table 6 illustrate the drainage lengths that will be used for mitigation purposes. Only a single side drainage of the hollowfills will be used for mitigation requirements. The top drainage of each hollowfill will be sloped toward the side to be used for mitigation to ensure that as much water as possible gets to the drainage used for mitigation. The top drainage of the hollowfills will be constructed at a 5 to 7 percent grade (on solid ground) and thus will function as a natural stream. Stream restoration in this section will follow profile and cross section plans that were collected at a stream of similar slope (Appendix E).

Based upon losses and gains at the project site, the client will need to offset the net loss of 1,955 feet (Table 6). To accomplish this, the client has agreed to pay an in-lieu-fee. Based upon the loss of 1,955 feet of stream, the client will need to pay an in-lieu-fee of \$291,600.00. This money will go to satisfy compensatory mitigation requirements and help meet the USACE's goal of no overall net loss of waters of the U.S. In-lieu-fee calculations are summarized in Table 7. The Stream Compensation Ratio Calculator forms that were used to calculate mitigation amounts are located in Appendix F. EII Calculation Spreadsheets for pre-disturbance, immediately after disturbance, and 30 years after disturbance are included in Appendices G, H, I. A summary of these data sheets is located in Table 8. Mitigation in these streams will follow restoration plans outlined in Section 5.0. Pictures of the streams are included with the EII Data Spreadsheets in Appendix G.

Restoration efforts will proceed as soon as mining operations have concluded. After restoration, certain habitat features will recover quickly while others will take time to mature. Both vegetative protection and riparian width will take time to come back, while the other eight parameters should come back more quickly (and in some instances even exceed pre-disturbance levels).

6.2 Site Protection

No site protection is proposed for the restored stream areas. To account for this, the risk factor used in the stream compensation ratio calculator, which is set at 20 percent for most projects, was set at 50.

Table 6. Stream compensation ratio calculator for proposed mitigation efforts at three streams in Knott County, Kentucky (Permit No. 860-0380, A. No. 6).

Impact Reach Name	Impacted Site			Mitigation Site								
	Length	Pre EII	Post EII	Mitigation Timing and Risk			EII			Mitigation (feet)		
				Start	Mature	Risk (%)	Pre-work	Immediately After	At Maturity	Length Required	Length Offered	Balance
Hollowfill #15 (ephemeral)	665	.20	0	2010	2040	50	0	.32	.37	386	386	0
Hollowfill #15 (intermittent)	1,064	.20	0	2010	2040	50	0	.32	.37	739	72	930
SS #106 (intermittent)	112	.20	0.1	2010	2040	50	0.1	.38	.43	39	39	0
Hollowfill #16 (ephemeral)	814	.38	0	2010	2040	50	0	.30	.35	953	953	0
Hollowfill #16 (intermittent)	1,025	.38	0	2010	2040	50	0	.30	.35	1,025	0	1,025
SS #107 (intermittent)	135	.39	0.1	2010	2040	50	0.1	.38	.43	136	135	0
Hollowfill #17 (ephemeral)	684	.25	0	2010	2040	50	0	.30	.34	535	535	0
SS #92 (intermittent)	105	.25	0.1	2010	2040	50	0.1	.30	.34	76	76	0
Total	4,604											1,955

- All mitigation will occur at the site of disturbance.

Table 7. In-lieu fee summary at three streams in Knott County, Kentucky (Permit No. 860-0380, A. No. 6).

Impact Reach Name	Stream Length Balance	EII	EIU	Compensatory Mitigation Ratio	In-Lieu Fee
Hollowfill #15 (ephemeral)	0	.20	0	-	0
Hollowfill #15 (intermittent)	930	.20	186	1.13	\$125,550.00
SS #106 (intermittent)	0	.20	0	-	0
Hollowfill #16 (ephemeral)	0	.38	0	-	0
Hollowfill #16 (intermittent)	1,025	.38	389.5	1.35	\$166,050.00
SS #107 (intermittent)	0	.39	0	-	0
Hollowfill #17 (ephemeral)	0	.25	0	-	0
SS #92 (intermittent)	0	.25	0	-	0
Total	1,955		575.5		\$291,600.00

Table 8. Individual habitat assessment parameters for hollowfills No. 15, 16, and 17 and sediment structures No. 106, 107, and 92 for present day, immediately after restoration, and 30 years after restoration, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).

Site	Time Period	Parameter										Total
		Epifaunal Substrate	Embeddedness	Velocity/Depth Regime	Sediment Deposition	Channel Flow Status	Channel Alteration	Frequency of Riffles	Bank Stability	Vegetative Protection	Riparian Width	
HF 15	Pre-disturbance	4	6	5	6	2	5	19	6	6	4	63
	5 Years	17	17	10	17	2	15	20	18	12	14	142
	30 Years	17	17	10	17	2	15	20	18	14	18	148
SS 106	Pre-disturbance	1	1	1	1	10	1	1	8	4	6	34
	5 Years	17	17	10	17	10	15	20	18	12	14	150
	30 Years	17	17	10	17	10	15	20	18	14	18	156
HF 16	Pre-disturbance	10	10	9	10	1	9	19	8	10	4	90
	5 Years	17	17	9	17	1	15	20	18	12	14	140
	30 Years	17	17	9	17	1	15	20	18	14	18	146
SS 107	Pre-disturbance	13	10	10	10	9	9	19	8	10	4	102
	5 Years	17	17	10	17	9	15	20	18	12	14	149
	30 Years	17	17	10	17	9	15	20	18	14	18	155
HF 17	Pre-disturbance	11	9	9	9	0	12	19	6	10	12	97
	5 Years	17	17	9	17	0	15	20	18	12	14	139
	30 Years	17	17	9	17	0	15	20	18	16	18	145
SS 92	Pre-disturbance	10	9	9	9	0	1	16	8	4	6	72
	5 Years	17	17	9	17	0	15	20	18	12	14	139
	30 Years	17	17	9	17	0	15	20	18	16	18	145

7.0 MONITORING

7.1 Monitoring and Long-term Management

Following the implementation of the restoration plan, a professional engineer will certify to the USACE that construction meets or exceeds planned goals. Following successful restoration, the restored areas will be monitored for five years. This monitoring plan will evaluate the success of the mitigation work and will allow for any necessary adjustments to assure the success of the restoration site. Annual monitoring reports will be submitted to the appropriate USACE office no later than 31 December of the year following completion of the restoration efforts. The annual monitoring reports will include an inspectors report and photographs with locations shown on project maps. If during the time that the restored areas are monitored, there are significant failures in the design of the restored streams, a revised mitigation plan will be submitted to fix any shortcomings in the original mitigation plan. If at the end of the five years the restoration efforts are deemed a success, the applicant shall be released from all permit obligations.

Monitoring will consist of grading the restored area yearly using the High Gradient Stream Restoration Sheets (Barbour et al. 1999). The following parameters will be monitored; pH, specific conductance, dissolved oxygen, epifaunal substrate, embeddedness, velocity/depth regime, sediment deposition, channel flow status, channel alteration, frequency of riffles, bank stability, vegetative protection, and riparian zone. Table 9 illustrates success standards and method of determination for each of these parameters.

Table 9. Factors to be considered when determining successful stream restoration, Knott County, Kentucky (Permit No. 860-0380, A. No. 6).

Parameter/Observation	Success Standards	Method of Determination
Field pH	Report Only	Field Meter
Specific Conductance	Report Only	Field Meter
Dissolved Oxygen	Report Only	Field Meter
Epifaunal Substrate	Minimum 70% favorable substrate	Pebble count; Estimate of available
Embeddedness	Maximum 20% embeddedness	Pebble count; measure embeddedness
Velocity/Depth Regime	Maintain step-pool or riffle-pool sequences similar to approved plans	Longitudinal profile
Sediment Deposition	Little or no enlargement of Islands or point bars and <5% of the bottom affected by sediment deposition	Pebble counts in pools
Channel Flow Status	Maintain width/depth ratio similar to accordance with plans	Determine from X-sections
Channel Alternation	Maintain minimal channelization similar to approved plans	Longitudinal profiles; X-sections
Frequency of Riffles	Maintain step-pool or riffle-pool sequences similar to approved plans	Longitudinal profile
Bank Stability	Banks stable	Bank Erosion Index; Observe density & depth of plant roots, near bank shear stress
Vegetative Protection	Approved width of riparian zone planted with minimum 300 stems/acre surviving	Measure replanted width; estimated stem count
Riparian Zone	Riparian zone with a variety of species alive and healthy	Measure replanted width; estimated stem count

7.2 Financial Assurances

Nally & Hamilton Enterprises, Inc. will assume all responsibility for success at the proposed mitigation site. Based upon this assumption of responsibility, no set aside fund is considered necessary.

8.0 RESPONSIBLE PARTIES

8.1 Applicant

Nally & Hamilton Enterprises, Inc.
P.O. Box 157
Bardstown, KY 40004
(606) 878-1500

8.2 Preparer of Restoration Plan

Apogee Environmental Consultants, Inc. (Joel Beverly)
P.O. Box 338
Ermine, KY 41815
(606) 633-7677

9.0 LITERATURE CITED

- Barbour, M.T., J. Gerritsen, B.D. Snyder, and J.B. Stribling. 1999. Rapid bioassessment protocols for use in wadeable streams and rivers: periphyton, benthic macroinvertebrates, and fish (2nd edition). The United States Environmental Protection Agency, Washington, D.C. EPA 841-B-99-002.
- Beverly, J. 2003. An aquatic biological assessment for a proposed surface mine near Littcarr, Knott County, Kentucky (Application # 860-0404). Final report submitted to Gress Engineering, Appalachia, VA. 13 pp plus appendices.
- Kentucky Division of Water. 2002. A macroinvertebrate bioassessment index for headwater streams of the Eastern Coalfield Region, Kentucky. Frankfort, KY. 48 pp.
- Rosgen, D. L. 1994. A classification of natural rivers. Catena, 169-199. Elsevier Science B. V. Amsterdam.
- Woods, A.J., Omernik, J.M., Martin, W.H., Pond, G.J., Andrews, W.M., Call, S.M., Comstock, J.A., and Taylor, D.D.. 2002. Ecoregions of Kentucky (color poster with map, descriptive text, summary tables, and photographs). Reston, VA., U.S. Geological Survey (map scale 1:1,000,000).

Appendix A

Completed High Gradient Stream Data Sheets

High Gradient Stream Data Sheet

STREAM NAME: <u>Sugar Branch</u>		LOCATION: <u>HF-16</u>		
STATION #: _____ MILE: _____		BASIN/WATERSHED: <u>N. Fork KY River</u>		
LAT.: _____ LONG.: _____		COUNTY: <u>Knott</u> USGS 7.5 TOPO: <u>Blackey</u>		
DATE: <u>14 Dec 05</u> TIME: <u>4:30</u> <input type="checkbox"/> AM <input checked="" type="checkbox"/> PM		INVESTIGATORS: <u>Joel Beverly</u>		
TYPE SAMPLE: <input type="checkbox"/> P-CHEM <input type="checkbox"/> Macroinvertebrate <input type="checkbox"/> FISH <input type="checkbox"/> BACT.				
WEATHER: Now Past 24 hours Has there been a heavy rain in the last 7 days? <input type="checkbox"/> <input type="checkbox"/> Heavy rain <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> <input type="checkbox"/> Steady rain Air Temperature _____ °C. Inches rainfall in past 24 hours _____ in. <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> Intermittent showers _____ % Cloud Cover <input type="checkbox"/> <input type="checkbox"/> Clear/sunny				
P-Chem: Temp(°C) <u>3.6</u> D.O. (mg/l) _____ %Saturation _____ pH(S.U.) <u>7.8</u> Cond. <u>270</u> <input type="checkbox"/> Grab				
INSTREAM WATERSHED FEATURES: Stream Width _____ ft Range of Depth _____ ft Average Velocity _____ ft/s Discharge _____ cfs Est. Reach Length _____		LOCAL WATERSHED FEATURES: <u>Predominant Surrounding Land Use: logging, roads</u> <input type="checkbox"/> Surface Mining <input type="checkbox"/> Construction <input checked="" type="checkbox"/> Forest <input type="checkbox"/> Deep Mining <input type="checkbox"/> Commercial <input type="checkbox"/> Pasture/Grazing <input checked="" type="checkbox"/> Oil Wells <input type="checkbox"/> Industrial <input type="checkbox"/> Silviculture <input type="checkbox"/> Land Disposal <input type="checkbox"/> Row Crops <input type="checkbox"/> Urban Runoff/Storm Sewers		
Hydraulic Structures: <input type="checkbox"/> Dams <input type="checkbox"/> Bridge Abutments <input type="checkbox"/> Island <input type="checkbox"/> Waterfalls <input type="checkbox"/> Other		Stream Flow: <input type="checkbox"/> Dry <input type="checkbox"/> Pooled <input checked="" type="checkbox"/> Low <input type="checkbox"/> Normal <input type="checkbox"/> Perennial <input type="checkbox"/> Intermittent <input type="checkbox"/> High <input type="checkbox"/> Very Rapid or Torrential <input checked="" type="checkbox"/> Ephemeral <input type="checkbox"/> Seep		
Riparian Vegetation: Dom. Tree/Shrub Taxa Dominate Type: <input checked="" type="checkbox"/> Trees <input checked="" type="checkbox"/> Shrubs <input type="checkbox"/> Grasses <input checked="" type="checkbox"/> Herbaceous Number of strata _____		Canopy Cover: <input type="checkbox"/> Fully Exposed (0-25%) <input type="checkbox"/> Partially Exposed (25-50%) <input checked="" type="checkbox"/> Partially Shaded (50-75%) <input type="checkbox"/> Fully Shaded (75-100%)		
Channel Alterations: <input type="checkbox"/> Dredging <input checked="" type="checkbox"/> Channelization (0 Full 0 Partial)				
Substrate <input type="checkbox"/> Est. <input type="checkbox"/> P.C.	Rifle _____ %	Run _____ %	Pool _____ %	
Silt/Clay (<0.06 mm)	See Pebble Count			
Sand (0.06 - 2 mm)				
Gravel (2-64 mm)				
Cobble (64 - 256 mm)				
Boulders (>256 mm)				
Bedrock				
Habitat	Condition Category			
Parameter	Optimal	Suboptimal	Marginal	Poor
1. Epifaunal Substrate/Available Cover	Greater than 70% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	40-70% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	20-40% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 20% stable habitat; lack of habitat is obvious; substrate unstable or lacking.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
2. Embeddedness	Gravel, cobble, and boulder particles are 0-25% surrounded by fine sediment. Layering of cobble provides diversity of niche space.	Gravel, cobble, and boulder particles are 25-50% surrounded by fine sediment.	Gravel, cobble, and boulder particles are 50-75% surrounded by fine sediment.	Gravel, cobble, and boulder particles are more than 75% surrounded by fine sediment.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
3. Velocity/Depth Regime	All four velocity/depth regimes present (slow-deep, slow-shallow, fast-deep, fast-shallow). (Slow is < 0.3 m/s, deep is > 0.5 m.)	Only 3 of the 4 regimes present (if fast-shallow is missing, score lower than if missing other regimes).	Only 2 of the 4 habitat regimes present (if fast-shallow or slow-shallow are missing, score low).	Dominated by 1 velocity/depth regime (usually slow-deep).
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0

HF-16

4. Sediment Deposition	Little or no enlargement of islands or point bars and less than 5% (<20% for low-gradient streams) of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment: 5-30% (20-50% for low-gradient) of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 30-50% (50-80% for low-gradient) of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 50% (80% for low-gradient) of the bottom changing frequently; pools almost absent due to substantial sediment deposition.
SCORE	20 19 18 17 16	15 14 13 12 11	(10) 9 8 7 6	5 4 3 2 1 0
5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 (1) 0
6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging (greater than past 20 yr.) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
SCORE	20 19 18 17 16	15 14 13 12 11	10 (9) 8 7 6	5 4 3 2 1 0
7. Frequency of Riffles (or bends)	Occurrence of riffles relatively frequent; ratio of distance between riffles divided by width of the stream <7:1 (generally 5 to 7); variety of habitat is key. In streams where riffles are continuous, placement of boulders or other large, natural obstruction is important.	Occurrence of riffles infrequent; distance between riffles divided by the width of the stream is between 7 to 15.	Occasional riffle or bend; bottom contours provide some habitat; distance between riffles divided by the width of the stream is between 15 to 25.	Generally all flat water or shallow riffles; poor habitat; distance between riffles divided by the width of the stream is a ratio of >25.
SCORE	20 (19) 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
Note: determine left or right side by facing downstream.				
SCORE (LB)	Left Bank 10 9	8 7 6	5 (4) 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 (4) 3	2 1 0
9. Vegetative Protection (score each bank)	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
SCORE (LB)	Left Bank 10 9	8 7 6	(5) 4 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	(5) 4 3	2 1 0
10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12-18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6-12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters; little or no riparian vegetation due to human activities.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	(2) 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	(2) 1 0

Total Score

NOTES/COMMENTS:

90

High Gradient Stream Data Sheet

STREAM NAME: <u>Sugar Branch</u>		LOCATION: <u>Pond 107</u>		
STATION #: _____ MILE: _____		BASIN/WATERSHED: <u>N. Fork KY River</u>		
LAT.: _____ LONG.: _____		COUNTY: <u>Knott</u> USGS 7.5 TOPO: <u>Blackey</u>		
DATE: <u>14 Dec 05</u> TIME: <u>3:45</u> <input type="checkbox"/> AM <input checked="" type="checkbox"/> PM		INVESTIGATORS: <u>Joel Beverly</u>		
TYPE SAMPLE: <input type="checkbox"/> P-CHEM <input type="checkbox"/> Macroinvertebrate <input type="checkbox"/> FISH <input type="checkbox"/> BACT.				
WEATHER: Now Past 24 hours Has there been a heavy rain in the last 7 days? <input type="checkbox"/> <input type="checkbox"/> Heavy rain <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> <input type="checkbox"/> Steady rain Air Temperature _____ °C. Inches rainfall in past 24 hours _____ in. <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> Intermittent showers _____ % Cloud Cover <input type="checkbox"/> <input type="checkbox"/> Clear/sunny				
P-Chem: Temp(°C) <u>3.6</u> D.O. (mg/l) _____ %Saturation _____ pH(S.U.) <u>7.8</u> Cond. <u>270</u> <input type="checkbox"/> Grab				
INSTREAM WATERSHED FEATURES: Stream Width _____ ft Range of Depth _____ ft Average Velocity _____ ft/s Discharge _____ cfs Est. Reach Length _____		LOCAL WATERSHED FEATURES: <u>Predominant Surrounding Land Use:</u> <u>logging, roads</u> <input type="checkbox"/> Surface Mining <input type="checkbox"/> Construction <input checked="" type="checkbox"/> Forest <input type="checkbox"/> Deep Mining <input type="checkbox"/> Commercial <input type="checkbox"/> Pasture/Grazing <input checked="" type="checkbox"/> Oil Wells <input type="checkbox"/> Industrial <input type="checkbox"/> Silviculture <input type="checkbox"/> Land Disposal <input type="checkbox"/> Row Crops <input type="checkbox"/> Urban Runoff/Storm Sewers		
<u>Hydraulic Structures:</u> <input type="checkbox"/> Dams <input type="checkbox"/> Bridge Abutments <input type="checkbox"/> Island <input type="checkbox"/> Waterfalls <input type="checkbox"/> Other		<u>Stream Flow:</u> <input type="checkbox"/> Dry <input type="checkbox"/> Pooled <input checked="" type="checkbox"/> Low <input type="checkbox"/> Normal <input type="checkbox"/> Perennial <input type="checkbox"/> Intermittent <input type="checkbox"/> High <input type="checkbox"/> Very Rapid or Torrential <input type="checkbox"/> Ephemeral <input type="checkbox"/> Seep		
<u>Riparian Vegetation:</u> Dom. Tree/Shrub Taxa Dominate Type: <input checked="" type="checkbox"/> Trees <input checked="" type="checkbox"/> Shrubs <input type="checkbox"/> Grasses <input checked="" type="checkbox"/> Herbaceous Number of strata _____		<u>Canopy Cover:</u> <input type="checkbox"/> Fully Exposed (0-25%) <input type="checkbox"/> Partially Exposed (25-50%) <input checked="" type="checkbox"/> Partially Shaded (50-75%) <input type="checkbox"/> Fully Shaded (75-100%)		
<u>Channel Alterations:</u> <input type="checkbox"/> Dredging <input checked="" type="checkbox"/> Channelization (0/Full 0/Partial)				
Substrate <input type="checkbox"/> Est. <input type="checkbox"/> P.C.	Riffle _____ %	Run _____ %	Pool _____ %	
Silt/Clay (<0.06 mm)	See Pebble			
Sand (0.06 – 2 mm)				
Gravel (2-64 mm)				
Cobble (64 – 256 mm)				
Boulders (>256 mm)		Count		
Bedrock				
Habitat	Condition Category			
Parameter	Optimal	Suboptimal	Marginal	Poor
1. Epifaunal Substrate/Available Cover	Greater than 70% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	40-70% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	20-40% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 20% stable habitat; lack of habitat is obvious; substrate unstable or lacking.
SCORE	20 19 18 17 16	15 14 (13) 12 11	10 9 8 7 6	5 4 3 2 1 0
2. Embeddedness	Gravel, cobble, and boulder particles are 0-25% surrounded by fine sediment. Layering of cobble provides diversity of niche space.	Gravel, cobble, and boulder particles are 25-50% surrounded by fine sediment.	Gravel, cobble, and boulder particles are 50-75% surrounded by fine sediment.	Gravel, cobble, and boulder particles are more than 75% surrounded by fine sediment.
SCORE	20 19 18 17 16	15 14 13 12 11	(10) 9 8 7 6	5 4 3 2 1 0
3. Velocity/Depth Regime	All four velocity/depth regimes present (slow-deep, slow-shallow, fast-deep, fast-shallow). (Sow is < 0.3 m/s, deep is > 0.5 m.)	Only 3 of the 4 regimes present (if fast-shallow is missing, score lower than if missing other regimes).	Only 2 of the 4 habitat regimes present (if fast-shallow or slow-shallow are missing, score low).	Dominated by 1 velocity/depth regime (usually slow-deep).
SCORE	20 19 18 17 16	15 14 13 12 11	(10) 9 8 7 6	5 4 3 2 1 0

Pond 107

4. Sediment Deposition	Little or no enlargement of islands or point bars and less than 5% (<20% for low-gradient streams) of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 5-30% (20-50% for low-gradient) of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 30-50% (50-80% for low-gradient) of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 50% (80% for low-gradient) of the bottom changing frequently; pools almost absent due to substantial sediment deposition.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr.) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
7. Frequency of Riffles (or bends)	Occurrence of riffles relatively frequent; ratio of distance between riffles divided by width of the stream <7:1 (generally 5 to 7); variety of habitat is key. In streams where riffles are continuous, placement of boulders or other large, natural obstruction is important.	Occurrence of riffles infrequent; distance between riffles divided by the width of the stream is between 7 to 15.	Occasional riffle or bend; bottom contours provide some habitat; distance between riffles divided by the width of the stream is between 15 to 25.	Generally all flat water or shallow riffles; poor habitat; distance between riffles divided by the width of the stream is a ratio of >25.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
Note: determine left or right side by facing downstream.				
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
9. Vegetative Protection (score each bank)	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone	Width of riparian zone 12-18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6-12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters; little or no riparian vegetation due to human activities.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0

Total Score

NOTES/COMMENTS:

107

High Gradient Stream Data Sheet

STREAM NAME: <u>Unnamed trib to D. Fork KY River</u>		LOCATION: <u>HF - 15</u>	
STATION #: _____ MILE: _____		BASIN/WATERSHED: <u>North Fork KY River</u>	
LAT.: _____ LONG.: _____		COUNTY: <u>Knott</u> USGS 7.5 TOPO: <u>Blackey</u>	
DATE: <u>2 Dec 05</u> TIME: <u>3:45</u> <input type="checkbox"/> AM <input checked="" type="checkbox"/> PM		INVESTIGATORS: <u>Joel Beverly</u>	
TYPE SAMPLE: <input type="checkbox"/> P-CHEM <input type="checkbox"/> Macroinvertebrate <input type="checkbox"/> FISH <input type="checkbox"/> BACT			
WEATHER: Now Past 24 hours Has there been a heavy rain in the last 7 days? <input type="checkbox"/> <input type="checkbox"/> Heavy rain <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> <input type="checkbox"/> Steady rain Air Temperature <u>39</u> °C. Inches rainfall in past 24 hours _____ in <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> Intermittent showers <u>0</u> % Cloud Cover <input checked="" type="checkbox"/> <input type="checkbox"/> Clear/sunny			
P-Chem: Temp(°C) <u>2.2</u> D.O. (mg/l) _____ %Saturation _____ pH(S.U.) <u>7.8</u> Cond. <u>410</u> <input type="checkbox"/> Grab			
INSTREAM WATERSHED FEATURES: Stream Width _____ ft Range of Depth _____ ft Average Velocity _____ ft/s Discharge _____ cfs Est. Reach Length _____		LOCAL WATERSHED FEATURES: <u>Predominant Surrounding Land Use:</u> <input checked="" type="checkbox"/> Surface Mining <input type="checkbox"/> Construction <input checked="" type="checkbox"/> Forest <input type="checkbox"/> Deep Mining <input type="checkbox"/> Commercial <input type="checkbox"/> Pasture/Grazing <input type="checkbox"/> Oil Wells <input type="checkbox"/> Industrial <input type="checkbox"/> Silviculture <input type="checkbox"/> Land Disposal <input type="checkbox"/> Row Crops <input type="checkbox"/> Urban Runoff/Storm Sewers	
Hydraulic Structures: <input type="checkbox"/> Dams <input type="checkbox"/> Bridge Abutments <input type="checkbox"/> Island <input type="checkbox"/> Waterfalls <input type="checkbox"/> Other <u>below fall (old)</u>		Stream Flow: <input checked="" type="checkbox"/> Dry <input type="checkbox"/> Pooled <input type="checkbox"/> Low <input type="checkbox"/> Normal <input type="checkbox"/> Perennial <input type="checkbox"/> Intermittent <input type="checkbox"/> High <input type="checkbox"/> Very Rapid or Torrential <input checked="" type="checkbox"/> Ephemeral <input type="checkbox"/> Seep	
Riparian Vegetation: Dom. Tree/Shrub Taxa Dominate Type: <input checked="" type="checkbox"/> Trees <input type="checkbox"/> Shrubs <input type="checkbox"/> Grasses <input type="checkbox"/> Herbaceous Number of strata _____		Channel Alterations: <input checked="" type="checkbox"/> Dredging <input checked="" type="checkbox"/> Channelization (0 Full 0 Partial)	
Substrate <input type="checkbox"/> Est. <input type="checkbox"/> P.C.		Rifle _____ %	
Silt/Clay (<0.06 mm)		Run _____ %	
Sand (0.06 - 2 mm)		Pool _____ %	
Gravel (2-64 mm)			
Cobble (64 - 256 mm)			
Boulders (>256 mm)			
Bedrock			
Habitat		Condition Category	
Parameter	Optimal	Suboptimal	Marginal
1. Epifaunal Substrate/Available Cover	Greater than 70% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	40-70% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	20-40% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6
2. Embeddedness	Gravel, cobble, and boulder particles are 0-25% surrounded by fine sediment. Layering of cobble provides diversity of niche space.	Gravel, cobble, and boulder particles are 25-50% surrounded by fine sediment.	Gravel, cobble, and boulder particles are 50-75% surrounded by fine sediment.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6
3. Velocity/Depth Regime	All four velocity/depth regimes present (slow-deep, slow-shallow, fast-deep, fast-shallow). (Slow is < 0.3 m/s, deep is > 0.5 m.)	Only 3 of the 4 regimes present (if fast-shallow is missing, score lower than if missing other regimes).	Only 2 of the 4 habitat regimes present (if fast-shallow or slow-shallow are missing, score low).
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6

HF-15

4. Sediment Deposition	Little or no enlargement of islands or point bars and less than 5% (<20% for low-gradient streams) of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 5-30% (20-50% for low-gradient) of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 30-50% (50-80% for low-gradient) of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 50% (80% for low-gradient) of the bottom changing frequently; pools almost absent due to substantial sediment deposition.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6 (6)	5 4 3 2 1 0
5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 (2) 1 0
6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr.) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	(5) 4 3 2 1 0
7. Frequency of Riffles (or bends)	Occurrence of riffles relatively frequent; ratio of distance between riffles divided by width of the stream <7:1 (generally 5 to 7); variety of habitat is key. In streams where riffles are continuous, placement of boulders or other large, natural obstruction is important.	Occurrence of riffles infrequent; distance between riffles divided by the width of the stream is between 7 to 15.	Occasional riffle or bend; bottom contours provide some habitat; distance between riffles divided by the width of the stream is between 15 to 25.	Generally all flat water or shallow riffles; poor habitat; distance between riffles divided by the width of the stream is a ratio of >25.
SCORE	20 (19) 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected. Note: determine left or right side by facing downstream.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 (3)	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 (3)	2 1 0
9. Vegetative Protection (score each bank)	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 (3)	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 (3)	2 1 0
10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >13 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12-18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6-12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters; little or no riparian vegetation due to human activities.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	(2) 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	(2) 1 0

Total Score

NOTES/COMMENTS:

44

High Gradient Stream Data Sheet

STREAM NAME: <u>Unnamed trib to Defeated Cr.</u>		LOCATION: <u>Pond 106</u> (existing pond)		
STATION #: _____ MILE: _____		BASIN/WATERSHED: <u>North Fork KY River</u>		
LAT.: _____ LONG.: _____		COUNTY: <u>Knott</u> USGS 7.5 TOPO: <u>Blackey</u>		
DATE: <u>2 Dec 06</u> TIME: <u>3:00</u> <input type="checkbox"/> AM <input checked="" type="checkbox"/> PM		INVESTIGATORS: <u>Joel Beverly</u>		
TYPE SAMPLE: <input type="checkbox"/> P-CHEM <input type="checkbox"/> Macroinvertebrate <input type="checkbox"/> FISH <input type="checkbox"/> BACT.				
WEATHER: Now _____ Past 24 hours _____		Has there been a heavy rain in the last 7 days?		
<input type="checkbox"/> Heavy rain		<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
<input type="checkbox"/> Steady rain		Air Temperature <u>39</u> °F		
<input checked="" type="checkbox"/> Intermittent showers		Inches rainfall in past 24 hours _____ in.		
<input type="checkbox"/> Clear/sunny		<u>0</u> % Cloud Cover		
P-Chem: Temp(°C) <u>22</u> D.O. (mg/l) _____ %Saturation _____ pH(S.U.) <u>7.8</u> Cond. <u>410</u> <input type="checkbox"/> Grab				
INSTREAM WATERSHED FEATURES:		LOCAL WATERSHED FEATURES:		
Stream Width _____ ft		Predominant Surrounding Land Use: <u>logging</u>		
Range of Depth _____ ft		<input checked="" type="checkbox"/> Surface Mining		
Average Velocity _____ ft/s		<input type="checkbox"/> Construction		
Discharge _____ cfs		<input type="checkbox"/> Deep Mining		
Est. Reach Length _____		<input type="checkbox"/> Oil Wells		
		<input type="checkbox"/> Land Disposal		
		<input type="checkbox"/> Commercial		
		<input type="checkbox"/> Industrial		
		<input type="checkbox"/> Row Crops		
		<input checked="" type="checkbox"/> Forest		
		<input type="checkbox"/> Pasture/Grazing		
		<input type="checkbox"/> Silviculture		
		<input type="checkbox"/> Urban Runoff/Storm Sewers		
Hydraulic Structures:		Stream Flow:		
<input type="checkbox"/> Dams <input type="checkbox"/> Bridge Abutments		<input type="checkbox"/> Dry <input type="checkbox"/> Pooled <input checked="" type="checkbox"/> Low <input type="checkbox"/> Normal		
<input type="checkbox"/> Island <input type="checkbox"/> Waterfalls		<input type="checkbox"/> High <input type="checkbox"/> Very Rapid or Torrential		
<input type="checkbox"/> Other _____		Stream Type:		
		<input type="checkbox"/> Perennial <input checked="" type="checkbox"/> Intermittent		
		<input type="checkbox"/> Ephemeral <input type="checkbox"/> Seep		
Riparian Vegetation: Dom. Tree/Shrub Taxa _____		Canopy Cover:		
Dominate Type: _____		<input type="checkbox"/> Fully Exposed (0-25%)		
<input checked="" type="checkbox"/> Trees <input type="checkbox"/> Shrubs		<input type="checkbox"/> Partially Exposed (25-50%)		
<input type="checkbox"/> Grasses <input type="checkbox"/> Herbaceous		<input checked="" type="checkbox"/> Partially Shaded (50-75%)		
Number of strata _____		<input type="checkbox"/> Fully Shaded (75-100%)		
		Channel Alterations:		
		<input checked="" type="checkbox"/> Dredging		
		<input type="checkbox"/> Channelization		
		(Full Partial)		
Substrate <input type="checkbox"/> Est. <input type="checkbox"/> P.C.	Rifle _____ %	Run _____ %	Pool _____ %	
Silt/Clay (<0.06 mm)	See Pebble Count			
Sand (0.06 - 2 mm)				
Gravel (2-64 mm)				
Cobble (64 - 256 mm)				
Boulders (>256 mm)				
Bedrock				
Habitat	Condition Category			
Parameter	Optimal	Suboptimal	Marginal	Poor
1. Epifaunal Substrate/Available Cover	Greater than 70% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	40-70% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	20-40% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 20% stable habitat; lack of habitat is obvious; substrate unstable or lacking.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
2. Embeddedness	Gravel, cobble, and boulder particles are 0-25% surrounded by fine sediment. Layering of cobble provides diversity of niche space.	Gravel, cobble, and boulder particles are 25-50% surrounded by fine sediment.	Gravel, cobble, and boulder particles are 50-75% surrounded by fine sediment.	Gravel, cobble, and boulder particles are more than 75% surrounded by fine sediment.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
3. Velocity/Depth Regime	All four velocity/depth regimes present (slow-deep, slow-shallow, fast-deep, fast-shallow). (Sow is < 0.3 m/s, deep is > 0.5 m.)	Only 3 of the 4 regimes present (if fast-shallow is missing, score lower than if missing other regimes).	Only 2 of the 4 habitat regimes present (if fast-shallow or slow-shallow are missing, score low).	Dominated by 1 velocity/depth regime (usually slow-deep).
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0

Pond 106

4. Sediment Deposition	Little or no enlargement of islands or point bars and less than 5% (<20% for low-gradient streams) of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 5-30% (20-50% for low-gradient) of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 30-50% (50-80% for low-gradient) of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 50% (80% for low-gradient) of the bottom changing frequently; pools almost absent due to substantial sediment deposition.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 (1) 0
5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.
SCORE	20 19 18 17 16	15 14 13 12 11	(10) 9 8 7 6	5 4 3 2 1 0
6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr.) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 (1) 0
7. Frequency of Riffles (or bends)	Occurrence of riffles relatively frequent; ratio of distance between riffles divided by width of the stream <7:1 (generally 5 to 7); variety of habitat is key. In streams where riffles are continuous, placement of boulders or other large, natural obstruction is important.	Occurrence of riffles infrequent; distance between riffles divided by the width of the stream is between 7 to 15.	Occasional riffle or bend; bottom contours provide some habitat; distance between riffles divided by the width of the stream is between 15 to 25.	Generally all flat water or shallow riffles; poor habitat; distance between riffles divided by the width of the stream is a ratio of >25.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 (1) 0
8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
Note: determine left or right side by facing downstream.				
SCORE (LB)	Left Bank 10 9	8 7 6	5 (4) 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 (4) 3	2 1 0
9. Vegetative Protection (score each bank)	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	(2) 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	(2) 1 0
10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12-18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6-12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters; little or no riparian vegetation due to human activities.
SCORE (LB)	Left Bank 10 9	8 7 6	5 (4) 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	(2) 1 0

Total Score

NOTES/COMMENTS:

34

High Gradient Stream Data Sheet

STREAM NAME: <u>Unnamed trib to Carr Cr. 4th</u>		LOCATION: <u>HF-17</u>	
STATION #: _____ MILE: _____		BASIN/WATERSHED: <u>N. Fork KY</u>	
LAT: <u>37°12'57"</u> LONG: <u>82°58'12"</u>		COUNTY: <u>Knott</u> USGS 7.5 TOPO: <u>Blackey</u>	
DATE: <u>8 Jan 05</u> TIME: <u>3:45</u> <input type="checkbox"/> AM <input checked="" type="checkbox"/> PM		INVESTIGATORS: <u>Joel Beverly</u>	
TYPE SAMPLE: <input type="checkbox"/> P-CHEM <input type="checkbox"/> Macroinvertebrate <input type="checkbox"/> FISH <input type="checkbox"/> BACT.			
WEATHER: Now _____ Past 24 hours _____ Has there been a heavy rain in the last 7 days? <input type="checkbox"/> <input type="checkbox"/> Heavy rain <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> <input type="checkbox"/> Steady rain Air Temperature _____ °C. Inches rainfall in past 24 hours <u>0</u> in. <input type="checkbox"/> <input type="checkbox"/> Intermittent showers _____ % Cloud Cover <input checked="" type="checkbox"/> <input checked="" type="checkbox"/> Clear/sunny			
P-Chem: Temp(°C) <u>5.6</u> D.O. (mg/l) _____ %Saturation <u>0</u> pH(S.U.) <u>7.3</u> Cond. <u>368</u> <input type="checkbox"/> Grab			
INSTREAM WATERSHED FEATURES: Stream Width _____ ft Range of Depth _____ ft Average Velocity _____ ft/s Discharge _____ cfs Est. Reach Length _____		LOCAL WATERSHED FEATURES: Predominant Surrounding Land Use: <u>gas wells</u> <input checked="" type="checkbox"/> Surface Mining <input type="checkbox"/> Construction <input checked="" type="checkbox"/> Forest <input type="checkbox"/> Deep Mining <input type="checkbox"/> Commercial <input type="checkbox"/> Pasture/Grazing <input type="checkbox"/> Oil Wells <input type="checkbox"/> Industrial <input type="checkbox"/> Silviculture <input type="checkbox"/> Land Disposal <input type="checkbox"/> Row Crops <input type="checkbox"/> Urban Runoff/Storm Sewers	
Hydraulic Structures: <input type="checkbox"/> Dams <input type="checkbox"/> Bridge Abutments <input type="checkbox"/> Island <input type="checkbox"/> Waterfalls <input type="checkbox"/> Other _____		Stream Flow: <input checked="" type="checkbox"/> Dry <input type="checkbox"/> Pooled <input type="checkbox"/> Low <input type="checkbox"/> Normal <input type="checkbox"/> Perennial <input type="checkbox"/> Intermittent <input type="checkbox"/> High <input type="checkbox"/> Very Rapid or Torrential <input checked="" type="checkbox"/> Ephemeral <input type="checkbox"/> Scarp	
Riparian Vegetation: Dom. Tree/Shrub Taxa _____ Dominate Type: <input checked="" type="checkbox"/> Trees <input checked="" type="checkbox"/> Shrubs <input type="checkbox"/> Grasses <input checked="" type="checkbox"/> Herbaceous Number of Strata _____		Canopy Cover: <input type="checkbox"/> Fully Exposed (0-25%) <input type="checkbox"/> Partially Exposed (25-50%) <input type="checkbox"/> Partially Shaded (50-75%) <input checked="" type="checkbox"/> Fully Shaded (75-100%)	
Channel Alterations: <input type="checkbox"/> Dredging <input checked="" type="checkbox"/> Channelization <input type="checkbox"/> Full <input type="checkbox"/> Partial			
Substrate Est. <input type="checkbox"/> P.C.	Riffle _____ %	Run _____ %	Pool _____ %
Silt/Clay (<0.06 mm)	See Pebble Count		
Sand (0.06 - 2 mm)			
Gravel (2-64 mm)			
Cobble (64 - 256 mm)			
Boulders (>256 mm)			
Bedrock			

Habitat	Condition Category			
Parameter	Optimal	Suboptimal	Marginal	Poor
1. Epifaunal Substrate/Available Cover	Greater than 70% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	40-70% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of new fall, but not yet prepared for colonization (may rate at high end of scale).	20-40% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 20% stable habitat; lack of habitat is obvious; substrate unstable or lacking
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
2. Embeddedness	Gravel, cobble, and boulder particles are 0-25% surrounded by fine sediment. Layering of cobble provides diversity of niche space.	Gravel, cobble, and boulder particles are 25-50% surrounded by fine sediment.	Gravel, cobble, and boulder particles are 50-75% surrounded by fine sediment.	Gravel, cobble, and boulder particles are more than 75% surrounded by fine sediment.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
3. Velocity/Depth Regime	All four velocity/depth regimes present (slow-deep, slow-shallow, fast-deep, fast-shallow). (Slow is < 0.3 m/s, deep is > 0.5 m.)	Only 3 of the 4 regimes present (if fast-shallow is missing, score lower than if missing other regimes).	Only 2 of the 4 habitat regimes present (if fast-shallow or slow-shallow are missing, score low).	Dominated by 1 velocity/depth regime (usually slow-deep).
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0

H-17

4. Sediment Deposition	Little or no enlargement of islands or point bars and less than 5% (<20% for low-gradient streams) of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 5-30% (20-50% for low-gradient) of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 30-50% (50-80% for low-gradient) of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 50% (80% for low-gradient) of the bottom changing frequently; pools almost absent due to substantial sediment deposition.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr.) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
7. Frequency of Riffles (or bends)	Occurrence of riffles relatively frequent; ratio of distance between riffles divided by width of the stream <7:1 (generally 5 to 7); variety of habitat is key. In streams where riffles are continuous, placement of boulders or other large, natural obstruction is important.	Occurrence of riffles infrequent; distance between riffles divided by the width of the stream is between 7 to 15.	Occasional riffle or bend; bottom contours provide some habitat; distance between riffles divided by the width of the stream is between 15 to 25.	Generally all flat water or shallow riffles; poor habitat; distance between riffles divided by the width of the stream is a ratio of >25.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
Note, determine left or right side by facing downstream.				
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
9. Vegetative Protection (score each bank)	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or nonwoody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e., parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12-18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6-12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters; little or no riparian vegetation due to human activities.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0

Total Score

NOTES/COMMENTS:

97

High Gradient Stream Data Sheet

STREAM NAME: <u>Unnamed trib to Carr Creek</u>		LOCATION: <u>SS # 96- A6</u>		
STATION #: _____ MILE: _____		BASIN/WATERSHED: <u>N. Fork KY</u>		
LAT.: <u>37°12'59"</u> LONG.: <u>82°58'12"</u>		COUNTY: <u>Knott</u> USGS 7.5 TOPO: <u>Black Key</u>		
DATE: <u>8 Jan 06</u> TIME: <u>3:00</u> <input type="checkbox"/> AM <input checked="" type="checkbox"/> PM		INVESTIGATORS: <u>Joel Beverly</u>		
TYPE SAMPLE: <input type="checkbox"/> P-CHEM <input type="checkbox"/> Macroinvertebrate <input type="checkbox"/> FISH <input type="checkbox"/> BACT.				
WEATHER: Now _____ Past 24 hours _____		Has there been a heavy rain in the last 7 days?		
<input type="checkbox"/> Heavy rain		<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
<input type="checkbox"/> Steady rain		Air Temperature _____ °C. Inches rainfall in past 24 hours <u>0</u> in.		
<input type="checkbox"/> Intermittent showers		<u>5</u> % Cloud Cover		
<input checked="" type="checkbox"/> Clear/sunny				
P-Chem. Temp(°C) <u>5.6</u> D.O. (mg/l) _____ %Saturation _____ pH(S.U.) <u>7.3</u> Cond. <u>36.8</u> <input type="checkbox"/> Grab				
INSTREAM WATERSHED FEATURES:		LOCAL WATERSHED FEATURES:		
Stream Width _____ ft		Predominant Surrounding Land Use: <u>Gas Wells</u>		
Range of Depth _____ ft		<input checked="" type="checkbox"/> Surface Mining <input type="checkbox"/> Construction <input checked="" type="checkbox"/> Forest		
Average Velocity _____ ft/s		<input type="checkbox"/> Deep Mining <input type="checkbox"/> Commercial <input type="checkbox"/> Pasture/Grazing		
Discharge _____ cfs		<input type="checkbox"/> Oil Wells <input type="checkbox"/> Industrial <input type="checkbox"/> Silviculture		
Est. Reach Length _____		<input type="checkbox"/> Land Disposal <input type="checkbox"/> Row Crops <input type="checkbox"/> Urban Runoff/Storm Sewers		
Hydraulic Structures:		Stream Flow:		
<input checked="" type="checkbox"/> Dams <input type="checkbox"/> Bridge Abutments		<input type="checkbox"/> Dry <input type="checkbox"/> Pooled <input type="checkbox"/> Low <input checked="" type="checkbox"/> Normal <input type="checkbox"/> Perennial <input checked="" type="checkbox"/> Intermittent		
<input type="checkbox"/> Island <input type="checkbox"/> Waterfalls		<input type="checkbox"/> High <input type="checkbox"/> Very Rapid or Torrential		
<input type="checkbox"/> Other _____		<input type="checkbox"/> Ephemeral <input type="checkbox"/> Seep		
Riparian Vegetation: Dom. Tree/Shrub Taxa _____		Canopy Cover:		
Dominate Type: <input checked="" type="checkbox"/> Trees <input checked="" type="checkbox"/> Shrubs		<input type="checkbox"/> Fully Exposed (0-25%)		
<input type="checkbox"/> Grasses <input checked="" type="checkbox"/> Herbaceous		<input type="checkbox"/> Partially Exposed (25-50%)		
Number of strata _____		<input type="checkbox"/> Partially Shaded (50-75%)		
		<input checked="" type="checkbox"/> Fully Shaded (75-100%)		
Channel Alterations:		Old Sediment		
<input checked="" type="checkbox"/> Dredging		control structure		
<input type="checkbox"/> Channelization		that has filled in		
<input type="checkbox"/> Full <input type="checkbox"/> Partial				
Substrate <input type="checkbox"/> Est. <input type="checkbox"/> P.C.	Riffle _____ %	Run _____ %	Pool _____ %	
Silt/Clay (<0.06 mm)	See Pebble	Count		
Sand (0.06 - 2 mm)				
Gravel (2-64 mm)				
Cobble (64 - 256 mm)				
Boulders (>256 mm)				
Bedrock				
Habitat	Condition Category			
Parameter	Optimal	Suboptimal	Marginal	Poor
1. Epifaunal Substrate/Available Cover	Greater than 70% of substrate favorable for epifaunal colonization and fish cover; mix of snags, submerged logs, undercut banks, cobble or other stable habitat and at stage to allow full colonization potential (i.e., logs/snags that are not new fall and not transient).	40-70% mix of stable habitat; well-suited for full colonization potential; adequate habitat for maintenance of populations; presence of additional substrate in the form of newfall, but not yet prepared for colonization (may rate at high end of scale).	20-40% mix of stable habitat; habitat availability less than desirable; substrate frequently disturbed or removed.	Less than 20% stable habitat; lack of habitat is obvious; substrate unstable or lacking.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
2. Embeddedness	Gravel, cobble, and boulder particles are 0-25% surrounded by fine sediment. Layering of cobble provides diversity of niche space.	Gravel, cobble, and boulder particles are 25-50% surrounded by fine sediment.	Gravel, cobble, and boulder particles are 50-75% surrounded by fine sediment.	Gravel, cobble, and boulder particles are more than 75% surrounded by fine sediment.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
3. Velocity/Depth Regime	All four velocity/depth regimes present (slow-deep, slow-shallow, fast-deep, fast-shallow). (Slow is < 0.3 m/s, deep is > 0.5 m.)	Only 3 of the 4 regimes present (if fast-shallow is missing, score lower than if missing other regimes).	Only 2 of the 4 habitat regimes present (if fast-shallow or slow-shallow are missing, score low).	Dominated by 1 velocity/depth regime (usually slow-deep).
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0

SS # 96 92

4. Sediment Deposition	Little or no enlargement of islands or point bars and less than 5% (<20% for low-gradient streams) of the bottom affected by sediment deposition.	Some new increase in bar formation, mostly from gravel, sand or fine sediment; 5-30% (20-50% for low-gradient) of the bottom affected; slight deposition in pools.	Moderate deposition of new gravel, sand or fine sediment on old and new bars; 30-50% (50-80% for low-gradient) of the bottom affected; sediment deposits at obstructions, constrictions, and bends; moderate deposition of pools prevalent.	Heavy deposits of fine material, increased bar development; more than 50% (80% for low-gradient) of the bottom changing frequently; pools almost absent due to substantial sediment deposition.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
5. Channel Flow Status	Water reaches base of both lower banks, and minimal amount of channel substrate is exposed.	Water fills >75% of the available channel; or <25% of channel substrate is exposed.	Water fills 25-75% of the available channel, and/or riffle substrates are mostly exposed.	Very little water in channel and mostly present as standing pools.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
6. Channel Alteration	Channelization or dredging absent or minimal; stream with normal pattern.	Some channelization present, usually in areas of bridge abutments; evidence of past channelization, i.e., dredging, (greater than past 20 yr.) may be present, but recent channelization is not present.	Channelization may be extensive; embankments or shoring structures present on both banks; and 40 to 80% of stream reach channelized and disrupted.	Banks shored with gabion or cement; over 80% of the stream reach channelized and disrupted. Instream habitat greatly altered or removed entirely.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
7. Frequency of Riffles (or bends)	Occurrence of riffles relatively frequent; ratio of distance between riffles divided by width of the stream <7:1 (generally 5 to 7); variety of habitat is key. In streams where riffles are continuous, placement of boulders or other large, natural obstruction is important.	Occurrence of riffles infrequent; distance between riffles divided by the width of the stream is between 7 to 15.	Occasional riffle or bend; bottom contours provide some habitat; distance between riffles divided by the width of the stream is between 15 to 25.	Generally all flat water or shallow riffles; poor habitat; distance between riffles divided by the width of the stream is a ratio of >25.
SCORE	20 19 18 17 16	15 14 13 12 11	10 9 8 7 6	5 4 3 2 1 0
8. Bank Stability (score each bank)	Banks stable; evidence of erosion or bank failure absent or minimal; little potential for future problems. <5% of bank affected. Note: determine left or right side by facing downstream.	Moderately stable; infrequent, small areas of erosion mostly healed over. 5-30% of bank in reach has areas of erosion.	Moderately unstable; 30-60% of bank in reach has areas of erosion; high erosion potential during floods.	Unstable; many eroded areas; "raw" areas frequent along straight sections and bends; obvious bank sloughing; 60-100% of bank has erosional scars.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
9. Vegetative Protection (score each bank)	More than 90% of the streambank surfaces and immediate riparian zone covered by native vegetation, including trees, understory shrubs, or non-woody macrophytes; vegetative disruption through grazing or mowing minimal or not evident; almost all plants allowed to grow naturally.	70-90% of the streambank surfaces covered by native vegetation, but one class of plants is not well-represented; disruption evident but not affecting full plant growth potential to any great extent; more than one-half of the potential plant stubble height remaining.	50-70% of the streambank surfaces covered by vegetation; disruption obvious; patches of bare soil or closely cropped vegetation common; less than one-half of the potential plant stubble height remaining.	Less than 50% of the streambank surfaces covered by vegetation; disruption of streambank vegetation is very high; vegetation has been removed to 5 centimeters or less in average stubble height.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0
10. Riparian Vegetative Zone Width (score each bank riparian zone)	Width of riparian zone >18 meters; human activities (i.e. parking lots, roadbeds, clear-cuts, lawns, or crops) have not impacted zone.	Width of riparian zone 12-18 meters; human activities have impacted zone only minimally.	Width of riparian zone 6-12 meters; human activities have impacted zone a great deal.	Width of riparian zone <6 meters; little or no riparian vegetation due to human activities.
SCORE (LB)	Left Bank 10 9	8 7 6	5 4 3	2 1 0
SCORE (RB)	Right Bank 10 9	8 7 6	5 4 3	2 1 0

Total Score

NOTES/COMMENTS:

72

Appendix B

Stratum Rank Key

Stratum Rank Key

Class	Description
-------	-------------

- | | |
|------|---|
| SR-9 | A sole dominant species; no other species exceed SR-2. |
| SR-8 | A species so outstanding as to be called the sole dominant; no other species exceeds SR-6. (Given to only one species) |
| SR-7 | A species sharing dominance. Given to one, but rarely two species (for example, oak – hickory). |
| SR-6 | A species sharing dominance with another, but markedly less important than the main dominant, or a species sharing dominance more or less equally with a number of species. |
| SR-5 | Given to the third or forth subdominant where there are two clear dominants, usually given only if all remaining species have low SRs. |
| SR-4 | A subordinate species, not a dominant or subdominant, but contributing significantly to both numbers and cover. |
| SR-3 | A species with three to several individuals furnishing substantial cover. |
| SR-2 | A species with two to several individuals, but infrequent in number and inconsequential in cover. |
| SR-1 | A species for which only a single individual is observed. |

Appendix C

Completed Data Sheets for Longitudinal Profiles, Pebble Counts, and Cross Sections



Longitudinal Profile Data Sheet – Hollow Fill 2

Project # 05.02 Project Name Carr Creek 404

Stream/Drainage Unnamed Trib. To Carr Creek Date 10/8/03

GPS: N 37°14'02.4" W 82°58'25.0"

County Knott State KY Quad Blackey

Point	Distance from Beg(ft)	Elevation (ft)	Stream Characteristic	Water depth (Tenths)	Bankfull (Tenths)
1	0.0	1209.6	Riffle	Dry	0.3
2	10.8	1210.2	Pool	Dry	
3	13.1	1209.7	Riffle	Dry	
4	17.3	1211.0	Pool	Dry	
5	36.2	1213.1	Riffle	Dry	
6	40.3	1212.4	Riffle	Dry	
7	43.9	1214.1	Pool	Dry	
8	57.2	1216.6	Riffle	Dry	
9	59.5	1216.1	Riffle	Dry	
10	65.7	1217.9	Pool	Dry	
11	68.5	1217.6	Riffle	Dry	
12	69.8	1217.9	Pool	Dry	
13	76.4	1218.6	Riffle	Dry	
14	99.7	1221.2	Riffle	Dry	0.8
15	112.0	1223.7	Riffle	Dry	
16	120.8	1224.5	Riffle	Dry	
17	138.1	1226.6	Riffle	Dry	
18	149.7	1228.4	Riffle	Dry	
19	153.1	1227.6	Riffle	Dry	
20	157.9	1228.2	Pool	Dry	
21	161.5	1231.6	Pool	Dry	0.8
22	189.5	1234.4	Riffle	Dry	
23	192.4	1234.1	Riffle	Dry	
24	195.0	1234.9	Pool	Dry	
25	216.3	1236.7	Riffle	Dry	
26	218.8	1236.0	Pool	Dry	
27	222.7	1237.2	Riffle	Dry	
28	225.5	1237.1	Riffle	Dry	
29	229.3	1239.0	Pool	Dry	
30	234.3	1239.9	Riffle	Dry	



Point	Distance from Beg (ft)	Elevation (ft)	Stream Characteristic	Water depth (Tenths)	Bankfull (Tenths)
31	235.4	1239.6	Pool		
32	241.2	1240.5	Riffle	Dry	
33	261	1242.7	Riffle	Dry	
34	265.2	1242.4	Riffle	Dry	
35	268.9	1243.6	Pool	Dry	
36	298.1	1245.6	Riffle	Dry	
37	307.2	1246.5	Riffle	Dry	
38	311.5	1246.0	Pool	Dry	0.9
39	316.1	1247.6	Pool	Dry	
40	336.2	1279.5	Riffle	Dry	
41	352.5	1252.1	Riffle	Dry	
42	354.1	1251.6	Riffle	Dry	
43	356.5	1252.5	Pool	Dry	
44	371.1	1255.2	Riffle	Dry	
45	373.1	1254.6	Riffle	Dry	
46	375.5	1256.1	Pool	Dry	
47	400	1260.4	Riffle	Dry	
48	402.9	1259.8	Riffle	Dry	
49	407.2	1262.9	Pool	Dry	
50	435.9	1266.0	Riffle	Dry	
51	441.9	1268.7	Pool Confluent	Dry	1.3
52	457.7	1270.7	Riffle	Dry	
53	460	1270.4	Riffle	Dry	
54	462.9	1271.8	Pool	Dry	
55	480.4	1275.1	Riffle	Dry	
56	489.5	1277.4	Riffle	Dry	
57	491.4	1276.8	Riffle	Dry	
58	495.3	1278.6	Pool	Dry	
59	508.6	1280.1	Riffle	Dry	
60	516.6	1281.5	Riffle	Dry	



Point	Distance from Beg(ft)	Elevation (ft)	Stream Characteristic	Water depth (Tenths)	Bankfull (Tenths)
61	530.4	1286.5	Pool	Dry	
62	532.7	1285.8	Riffle	Dry	
63	535.4	1287.3	Pool	Dry	
64	545.1	1292.0	Riffle	Dry	
65	560.7	1295.5	Riffle	Dry	
66	568.7	1297.7	Riffle	Dry	
67	584.9	1300	Riffle	Dry	
68	586.2	1299.7	Riffle	Dry	
69	591.7	1302.2	Pool	Dry	
70	606.5	1306.7	Riffle	Dry	
71	610.3	1306.5	Pool Confluent	Dry	1.1
72	612.1	1307.3	Riffle	Dry	
73	622.7	1312.1	Riffle	Dry	
74	629.4	1316.7	Riffle	Dry	
75	634	1318	Riffle	Dry	0.8
76	648.6	1320.1	Riffle	Dry	
77	655.8	1319.6	Pool	Dry	
78	657.9	1320.8	Riffle	Dry	
79	671.2	1322.7	Riffle	Dry	
80	672.7	1324	Riffle	Dry	
81	675.2	1324.3	Riffle	Dry	
82	678.9	1326.7	Riffle	Dry	
83	688.2	1327.9	Riffle	Dry	
84	695.7	1331.6	Riffle	Dry	
85	703.1	1332.8	Riffle	Dry	
86	707.1	1335.7	Riffle	Dry	
87	717.5	1338.5	Riffle	Dry	
88	724	1341.5	Riffle	Dry	0.6
89	726.4	1343.4	Riffle	Dry	
90	730.7	1344.6	Riffle	Dry	



Point	Distance from Beg(ft)	Elevation (ft)	Stream Characteristic	Water depth (Tenths)	Bankfull (Tenths)
91	735.1	1348.1	Riffle	Dry	
92	744.6	1350.8	Riffle	Dry	
93	748.8	1354.1	Riffle	Dry	
94	752.4	1356.5	Riffle	Dry	
95	762	1358.6	Riffle	Dry	
96	763.3	1359.7	Riffle	Dry	0.6
97	766.8	1360.9	Riffle	Dry	
98	769	1360.6	Pool	Dry	
99	773.1	1362.6	Riffle	Dry	
100					
101	Tributary				
102	0.0	1266	Pool	Dry	
103	3.2	1268.1	Riffle	Dry	0.6
104	14.9	1269.4	Riffle	Dry	
105	17.5	1268.4	Pool	Dry	
106	21.1	1270.8	Riffle	Dry	
107	34.7	1273.8	Riffle	Dry	
108	36.3	1273.4	Pool	Dry	
109	41.3	1275.9	Riffle	Dry	
110	52.3	1277.8	Riffle	Dry	
111	72.9	1283.4	Riffle	Dry	
112	76.4	1285.1	Riffle	Dry	
113	87.8	1286.7	Riffle	Dry	
114	98.5	1290.4	Riffle	Dry	
115					
116	Tributary				
117	0.0	1306.7	Pool	Dry	
118	3.1	1306.9	Riffle	Dry	
119	7.9	1311.5	Riffle	Dry	
120	12.4	1311.9	Riffle	Dry	



Point	Distance from Beg (ft)	Elevation (ft)	Stream Characteristic	Water depth (Tenths)	Bankfull (Tenths)
121	13.6	1311.4	Pool	Dry	
122	17.2	1313.9	Riffle	Dry	
123	21	1314.5	Riffle	Dry	
124	22.9	1314.2	Pool	Dry	1.2
125	25.6	1315.9	Riffle	Dry	
126	27.2	1315.6	Pool	Dry	
127	30.8	1316.8	Riffle	Dry	
128	35	1317.1	Riffle	Dry	
129	39.3	1317.7	Riffle	Dry	
130	48.8	1319.1	Riffle	Dry	
131	51.4	1320	Riffle	Dry	
132	53.8	1319.5	Pool	Dry	
133	56.1	1320.9	Riffle	Dry	
134	57.2	1320.7	Riffle	Dry	
135	59.5	1321.8	Riffle	Dry	
136	69.8	1324.6	Riffle	Dry	
127	74.9	1327.7	Riffle	Dry	
138	77.1	1327.8	Riffle	Dry	
139	79.1	1328.9	Riffle	Dry	
140	87.9	1332.2	Riffle	Dry	
141	97.8	1334.1	Riffle	Dry	
142	100.6	1334.7	Riffle	Dry	
143	103.2	1335	Pool	Dry	0.7
144	106.3	1337.3	Riffle	Dry	
145	109	1336.9	Pool	Dry	
146	113.4	1339.9	Riffle	Dry	
147	117.3	1340.9	Riffle	Dry	
148	119.6	1342.3	Riffle	Dry	
149	126.5	1342.9	Riffle	Dry	
150	128.1	1344.3	Riffle	Dry	0.6

****(Family Level Taxonomy - Riffle Only
Sample)****

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: HF-15
Unnamed Tributary to Defeated Creek

**Assessment
Objectives:**

EII	Model
NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)
0.20	Ecological Integrity Index (Habitat Integrity + Conductivity)

Variables	Measure	Units
<u>RBP Habitat Parameters</u>		
1. Epifaunal Substrate	4	no units (0-20)
2. Embeddedness	6	no units (0-20)
3. Velocity/Depth Regime	5	no units (0-20)
4. Sediment Deposition	6	no units (0-20)
5. Channel Flow Status	2	no units (0-20)
6. Channel Alteration	5	no units (0-20)
7. Freq. Of Riffles (bends)	19	no units (0-20)
8. Bank stability (both combined)	6	no units (0-20)
9. Veg. Protection (both combined)	6	no units (0-20)
10. Riparian Width (both combined)	4	no units (0-20)
Total Habitat Score	63	no units
Habitat Integrity Index		0.10
<u>Macroinvertebrate Data - Family Level</u>		

(Riffle Only)

11. Family Taxa
Richness

0

of taxa
sampled

12. Family EPT
Richness

0

of EPT
species
sampled

13. % Ephemeroptera
14. % Chironomidae &
Oligochaeta

0

% Mayflies (0-
100)

0

% Midges &
Worms (0-100)

16. mFBI

0

no units

Macroinvertebrate Benthos	NA	0	0	0	0	0
Confidence		410				



****(Family Level Taxonomy - Riffle Only
Sample)****

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: Pond 106

Assessment Objectives: Unnamed Tributary to Defeated Creek

EII	Model
NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)
0.20	Ecological Integrity Index (Habitat Integrity + Conductivity)

Variables	Measure	Units
RBP Habitat Parameters		
1. Epifaunal Substrate	1	no units (0-20)
2. Embeddedness	1	no units (0-20)
3. Velocity/Depth Regime	1	no units (0-20)
4. Sediment Deposition	1	no units (0-20)
5. Channel Flow Status	10	no units (0-20)
6. Channel Alteration	1	no units (0-20)
7. Freq. Of Riffles (bends)	1	no units (0-20)
8. Bank stability (both combined)	8	no units (0-20)
9. Veg. Protection (both combined)	4	no units (0-20)
10. Riparian Width (both combined)	6	no units (0-20)
Total Habitat Score	34	no units
Habitat Integrity Index		0.10
Macroinvertebrate Data - Family Level		

(Riffle Only)

11. Family Taxa Richness	0	# of taxa sampled	
12. Family EPT Richness	0	# of EPT species sampled	
13. % Ephemeroptera	0	% Mayflies (0-100)	
14. % Chironomidae & Oligochaeta	0	% Midges & Worms (0-100)	
16. mFBI	0	no units	
Macroinvertebrate Bioassessment	NA	no units	NA
Conductivity	410	microMhos	0.31



****(Family Level Taxonomy - Riffle Only
Sample)****

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: HF 16

Assessment Objectives: Sugar Branch

EII	Model
NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)
0.38	Ecological Integrity Index (Habitat Integrity + Conductivity)

Variables	Measure	Units
RBP Habitat Parameters		
1. Epifaunal Substrate	10	no units (0-20)
2. Embeddedness	10	no units (0-20)
3. Velocity/Depth Regime	9	no units (0-20)
4. Sediment Deposition	10	no units (0-20)
5. Channel Flow Status	1	no units (0-20)
6. Channel Alteration	9	no units (0-20)
7. Freq. Of Riffles (bends)	19	no units (0-20)
8. Bank stability (both combined)	8	no units (0-20)
9. Veg. Protection (both combined)	10	no units (0-20)
10. Riparian Width (both combined)	4	no units (0-20)

Total Habitat Score

90

no units

Subindex

Habitat Integrity Index

0.10

**Macroinvertebrate
Data - Family Level**

(Rifle Only)

- 11. Family Taxa Richness
- 12. Family EPT Richness
- 13. % Ephemeroptera
- 14. % Chironomidae & Oligochaeta
- 16. mFBI

	0
	0
	0
	0
	0

of taxa sampled
of EPT species sampled
% Mayflies (0-100)
% Midges & Worms (0-100)
no units

MACROINVERTEBRATE BIODIVERSITY	NA	NO DATA
Conductivity	270	MACROINVERTEBRATE BIODIVERSITY



****(Family Level Taxonomy - Riffle Only
Sample)****

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: Pond-107

Assessment Objectives: Sugar Branch

EI	Model
NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)
0.39	Ecological Integrity Index (Habitat Integrity + Conductivity)

Variables	Measure	Units
<u>RBP Habitat Parameters</u>		
1. Epifaunal Substrate	13	no units (0-20)
2. Embeddedness	10	no units (0-20)
3. Velocity/Depth Regime	10	no units (0-20)
4. Sediment Deposition	10	no units (0-20)
5. Channel Flow Status	9	no units (0-20)
6. Channel Alteration	9	no units (0-20)
7. Freq. Of Riffles (bends)	19	no units (0-20)
8. Bank stability (both combined)	8	no units (0-20)
9. Veg. Protection (both combined)	10	no units (0-20)
10. Riparian Width (both combined)	4	no units (0-20)

Total Habitat Score

102

no units

Subindex

Habitat Integrity Index

0.39

**Macroinvertebrate
Data - Family Level**


(Rifle Only)

- 11. Family Taxa Richness
- 12. Family EPT Richness
- 13. % Ephemeroptera
- 14. % Chironomidae & Oligochaeta
- 16. mFBI

	0
	0
	0
	0
	0

of taxa sampled
of EPT species sampled
% Mayflies (0-100)
% Midges & Worms (0-100)
no units

Macroinvertebrate Bioassessment	NA	NO DATA	NA
Conductivity	270	Microhardness	0.25



****(Family Level Taxonomy - Riffle Only
Sample)****

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: HF-17

Unnamed Tributary to Carr Creek Lake

**Assessment
Objectives:**

EII	Model
NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)
0.25	Ecological Integrity Index (Habitat Integrity + Conductivity)

Variables	Measure	Units
RBP Habitat Parameters		
1. Epifaunal Substrate	11	no units (0-20)
2. Embeddedness	9	no units (0-20)
3. Velocity/Depth Regime	9	no units (0-20)
4. Sediment Deposition	9	no units (0-20)
5. Channel Flow Status	0	no units (0-20)
6. Channel Alteration	12	no units (0-20)
7. Freq. Of Riffles (bends)	19	no units (0-20)
8. Bank stability (both combined)	6	no units (0-20)
9. Veg. Protection (both combined)	10	no units (0-20)
10. Riparian Width (both combined)	12	no units (0-20)

Total Habitat Score

97

no units

Subindex

Habitat Integrity Index

0-100

**Macroinvertebrate
Data - Family Level**

****(Family Level Taxonomy - Riffle Only
Sample)****

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: Pond 92
Unnamed Tributary to Carr Creek Lake

Assessment Objectives:

EII	Model
NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)
0.25	Ecological Integrity Index (Habitat Integrity + Conductivity)

Variables	Measure	Units
RBP Habitat Parameters		
1. Epifaunal Substrate	10	no units (0-20)
2. Embeddedness	9	no units (0-20)
3. Velocity/Depth Regime	9	no units (0-20)
4. Sediment Deposition	9	no units (0-20)
5. Channel Flow Status	0	no units (0-20)
6. Channel Alteration	1	no units (0-20)
7. Freq. Of Riffles (bends)	16	no units (0-20)
8. Bank stability (both combined)	8	no units (0-20)
9. Veg. Protection (both combined)	4	no units (0-20)
10. Riparian Width (both combined)	6	no units (0-20)

Total Habitat Score

72

no units

Subindex

Habitat Integrity Index

0.10

Stream Compensation Ratio Calculator version 3.4

Inputs		Impacted Site				Mitigation Site																											
Time Horizon: 75		Impact Year: 2007				Mitigation Work Timing & Risk				Ecological Integrity Index																							
Project ID#	DNR # 880-0360, A.6	Ecological Integrity Index		Length	Balance					Pre-Work			Immediately After Work			At Maturity																	
Project Name: Sugar Branch		Pre-Impact		Post-Impact	(ft)	(ft)	Mitigation Reach (MR) Name			Year Started			Year Matured			Failure Risk			Mitigation (Length Required)			Mitigation (Length Offered)											
Impact Reach (IR):		0.20		0.00	665	0	HF 16 (ephemeral)			2007			2010			50			0.00			0.32			0.37			386			386		
Reach Continued		0.20		0.00		0																											
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																											
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																											
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																											
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																											
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																											
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																											
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																											
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																											
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																											
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																											
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																											

Outputs		Ecological Integrity Compensation Ratios				Ratio	
Impact Reach vs Mitigation Reach		(mitigation site feet per impact site foot)					
IR vs MR1		>>				0.58	
IR vs MR2		(see note 1)				#DIV/0!	
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!

Instructions

1) Describe the project impacts:

a) Indicate when the impact(s) will take place (i.e., Impact Year)

b) Estimate the Ecological Integrity (EI) prior to project impacts (i.e., Pre-Impact)

c) Predict Ecological Integrity (EI) after the proposed impacts occur (i.e., Post-Impact)

d) Prescribe the length of stream reach represented by this proposed impact

2) Describe the proposed mitigation used to offset proposed impacts:

a) Indicate when the proposed mitigation will take place (i.e., Year Started)

b) Predict when the mitigation project will reach maturity (i.e., Year Matured)

c) Estimate the Risk of Failure for the specific proposed mitigation site and plan

d) Estimate the Ecological Integrity of the proposed mitigation site before any work is done (i.e., Pre-Work, Immediately After Work, and At Maturity)

e) Indicate the linear distance of the proposed mitigation offered to offset proposed impacts

f) If necessary, (indicated by a balance > 0 in Column P), continue with additional mitigation sites

User Notes:

1) User only needs to fill out the gray shaded boxes.

2) Use a separate spreadsheet for each homogeneous impact reach to be mitigated

[illegible]

- 1) Describe the project impacts:
 - a) Indicate when the impact(s) will take place (i.e., Impact Year)
 - b) Estimate the Ecological Integrity (EI) prior to project impacts (i.e., Pre-Impact)
 - c) Predict Ecological Integrity (EI) after the proposed impacts occur (i.e., Post-Impact)
 - d) Prescribe the length of stream reach represented by this proposed impact
- 2) Describe the proposed mitigation used to offset proposed impacts:
 - a) Indicate when the proposed mitigation will take place (i.e., Year Started)
 - b) Predict when the mitigation project will reach maturity (i.e., Year Matured)
 - c) Estimate the Risk of Failure for the specific proposed mitigation site and plan
 - d) Estimate the Ecological Integrity of the proposed mitigation site before any work is done (i.e., Pre-Work), Immediately After Work, and At Maturity
 - a) Indicate the linear distance of the proposed mitigation offered to offset proposed impacts
 - f) If necessary, (indicated by a balance > 0 in Column P), continue with additional mitigation sites

User Notes:

- 1) User only needs to fill out the gray shaded boxes
- 2) Use a separate spreadsheet for each homogeneous impact reach to be mitigated

Stream Compensation Ratio Calculator Version 3.4

Inputs		Time Horizon: 76		Impacted Site		Mitigation Site																					
Project ID #:		DNR # 860-0380, A.6		Impact Year: 2007		Mitigation Work Timing & Risk				Ecological Integrity Index			Mitigation														
Project Name:		Sugar Branch		Ecological Integrity Index																							
Impact Reach (IR):		Pre-Impact		Post-Impact		Length (ft)		Balance (ft)		Mitigation Reach (MR) Name		Year Started		Year Matured		Failure Risk		Pre-Work		Immediately After Work		At Maturity		Mitigation (Length Required)		Mitigation (Length Offered)	
HF 16 (ephemeral)		0.38		0.00		814				HF 16 (ephemeral)		2007		2010		50		0.00		0.30		0.35		963		963	
Reach Continued		0.38		0.00		0																		#DIV/0!			
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																		#DIV/0!			
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																		#DIV/0!			
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																		#DIV/0!			
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																		#DIV/0!			
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																		#DIV/0!			
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																		#DIV/0!			
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																		#DIV/0!			
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																		#DIV/0!			
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																		#DIV/0!			

Outputs		Ecological Integrity Compensation Ratios		Ratio		Instructions	
Impact Reach vs Mitigation Reach		(mitigation site feet per impact site foot)					
IR vs MR1		1.17				1) Describe the project impacts:	
IR vs MR2		(see note 15) #DIV/0!				a) Indicate when the impact(s) will take place (i.e., Impact Year)	
#DIV/0!		#DIV/0! #DIV/0!		#DIV/0! #DIV/0!		b) Estimate the Ecological Integrity (EI) prior to project impacts (i.e., Pre-Impact)	
#DIV/0!		#DIV/0! #DIV/0!		#DIV/0! #DIV/0!		c) Predict Ecological Integrity (EI) after the proposed impacts occur (i.e., Post-Impact)	
#DIV/0!		#DIV/0! #DIV/0!		#DIV/0! #DIV/0!		d) Prescribe the length of stream reach represented by this proposed impact	
#DIV/0!		#DIV/0! #DIV/0!		#DIV/0! #DIV/0!		2) Describe the proposed mitigation used to offset proposed impacts:	
#DIV/0!		#DIV/0! #DIV/0!		#DIV/0! #DIV/0!		a) Indicate when the proposed mitigation will take place (i.e., Year Started)	
#DIV/0!		#DIV/0! #DIV/0!		#DIV/0! #DIV/0!		b) Predict when the mitigation project will reach maturity (i.e., Year Matured)	
#DIV/0!		#DIV/0! #DIV/0!		#DIV/0! #DIV/0!		c) Estimate the Risk of Failure for the specific proposed mitigation site and plan	
#DIV/0!		#DIV/0! #DIV/0!		#DIV/0! #DIV/0!		d) Estimate the Ecological Integrity of the proposed mitigation site before any work is done (i.e., Pre-Work), immediately After Work, and At Maturity	
#DIV/0!		#DIV/0! #DIV/0!		#DIV/0! #DIV/0!		e) Indicate the linear distance of the proposed mitigation offered to offset proposed impacts	
#DIV/0!		#DIV/0! #DIV/0!		#DIV/0! #DIV/0!		f) If necessary, (indicated by a balance > 0 in Column P), continue with additional mitigation sites	
#DIV/0!		#DIV/0! #DIV/0!		#DIV/0! #DIV/0!		User Notes:	
						1) User only needs to fill out the gray shaded boxes	
						2) Use a separate spreadsheet for each homogeneous impact reach to be mitigated	

Stream Compensation Ratio Calculator version 3.4

Inputs		Time Horizon: 76		Impacted Site		Mitigation Site													
Project ID #:		DNR # 860-0380, A.6		Impact Year: 2007		Mitigation Work Timing & Risk					Ecological Integrity Index			Mitigation					
Project Name:		Sugar Branch		Ecological Integrity Index															
Impact Reach (IR):		Pre-Impact		Post-Impact		Mitigation Reach (MR) Name					Pre-Work			Immediately After Work			At Maturity		
HF 18 (Intermittent)		0.38		0.00		1026													
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!					#DIV/0!			#DIV/0!			#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!					#DIV/0!			#DIV/0!			#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!					#DIV/0!			#DIV/0!			#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!					#DIV/0!			#DIV/0!			#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!					#DIV/0!			#DIV/0!			#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!					#DIV/0!			#DIV/0!			#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!					#DIV/0!			#DIV/0!			#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!					#DIV/0!			#DIV/0!			#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!					#DIV/0!			#DIV/0!			#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!					#DIV/0!			#DIV/0!			#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!					#DIV/0!			#DIV/0!			#DIV/0!		

Outputs		Ecological Integrity Compensation Ratios				Ratio		Instructions
Impact Reach vs Mitigation Reach		(mitigation site feet per impact site foot)						
IR vs MR1		(see note 1)				#DIV/0!		
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	1) Describe the project impacts:
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	a) Indicate when the impact(s) will take place (i.e., Impact Year)
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	b) Estimate the Ecological Integrity (EI) prior to project impacts (i.e., Pre-Impact)
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	c) Predict Ecological Integrity (EI) after the proposed impacts occur (i.e., Post-Impact)
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	d) Prescribe the length of stream reach represented by this proposed impact
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	2) Describe the proposed mitigation used to offset proposed impacts:
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	a) Indicate when the proposed mitigation will take place (i.e., Year Started)
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	b) Predict when the mitigation project will reach maturity (i.e., Year Matured)
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	c) Estimate the Risk of Failure for the specific proposed mitigation site and plan
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	d) Estimate the Ecological Integrity of the proposed mitigation site before any work is done (i.e., Pre-Work), Immediately After Work, and At Maturity
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	e) Indicate the linear distance of the proposed mitigation offered to offset proposed impacts
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	f) If necessary, (indicated by a balance > 0 in Column P), continue with additional mitigation sites
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	User Notes:
1) User only needs to fill out the gray shaded boxes								
2) Use a separate spreadsheet for each homogeneous impact reach to be mitigated								

Stream Compensation Ratio Calculator Version 3.4

Inputs		Time Horizon: 75		Impacted Site		Mitigation Site																													
Project ID #:		DNR # 860-0380, A.6		Impact Year: 2007		Mitigation Work Timing & Risk				Ecological Integrity Index			Mitigation		Mitigation																				
Project Name:		Sugar Branch		Ecological Integrity Index																															
Impact Reach (IR):		Pre-Impact		Post-Impact		Length (ft)		Balance (ft)		Mitigation Reach (MRI) Name				Pre-Work			Immediately After Work			At Maturity			Mitigation (Length Required)		Mitigation (Length Offered)										
SS-107		0.39		0.10		135				SS-107				2010			2040			60%			0.10			0.38			0.43			135		135	
Reach Continued		0.39		0.10				1		SS-108				2010			2040			60%			0.10			0.38			0.43			1		1	
Reach Continued		0.39		0.10				0																								#DIV/0!			
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																					#DIV/0!						
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																					#DIV/0!						
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																					#DIV/0!						
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																					#DIV/0!						
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																					#DIV/0!						
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																					#DIV/0!						
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																					#DIV/0!						
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																					#DIV/0!						
#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!		#DIV/0!																					#DIV/0!						

Outputs		Ecological Integrity Compensation Ratios				Ratio	
Impact Reach vs Mitigation Reach		(mitigation site feet)				per impact site foot	
IR vs MR1						1.01	
IR vs MR2						1.01	
IR vs MR3		(see note 1)				#DIV/0!	
#DIV/0!		#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	
#DIV/0!		#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	
#DIV/0!		#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	
#DIV/0!		#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	
#DIV/0!		#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	
#DIV/0!		#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	
#DIV/0!		#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	
#DIV/0!		#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	

Instructions	
1) Describe the project impacts:	
a) Indicate when the impact(s) will take place (i.e., Impact Year)	
b) Estimate the Ecological Integrity (EI) prior to project impacts (i.e., Pre-Impact)	
c) Predict Ecological Integrity (EI) after the proposed impacts occur (i.e., Post-Impact)	
d) Prescribe the length of stream reach represented by this proposed impact	
2) Describe the proposed mitigation used to offset proposed impacts:	
a) Indicate when the proposed mitigation will take place (i.e., Year Started)	
b) Predict when the mitigation project will reach maturity (i.e., Year Matured)	
c) Estimate the Risk of Failure for the specific proposed mitigation site and plan	
d) Estimate the Ecological Integrity of the proposed mitigation site before any work is done (i.e., Pre-Work), Immediately After Work, and At Maturity	
e) Indicate the linear distance of the proposed mitigation offered to offset proposed impacts	
f) If necessary, (indicated by a balance > 0 in Column P), continue with additional mitigation sites	
User Notes:	
1) User only needs to fill out the gray shaded boxes	
2) Use a separate spreadsheet for each homogeneous impact reach to be mitigated	

Stream Compensation Ratio Calculator Version 3.4

Inputs		Time Horizon: 75		Impacted Site		Mitigation Site									
Project ID #:		DNR # 060-0380, A.6		Impact Year: 2007		Mitigation Work Timing & Risk				Ecological Integrity Index			Mitigation		
Project Name:		Sugar Branch		Ecological Integrity Index											
				Length Balance		Year Started Year Matured Failure Risk				Pre-Work Immediately After Work At Maturity			Mitigation (Length Required) Mitigation (Length Offered)		
Impact Reach (IR):		Pre-Impact		Post-Impact		Mitigation Reach (MR) Name									
HF 17 (ephemeral)		0.25		0.00		HF 17 (ephemeral)				0.00 0.30 0.34			635 635		
Reach Continued		0.25		0.00									#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!									#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!									#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!									#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!									#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!									#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!									#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!									#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!									#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!									#DIV/0!		
#DIV/0!		#DIV/0!		#DIV/0!									#DIV/0!		

Outputs		Ecological Integrity Compensation Ratios		Ratio	
Impact Reach vs Mitigation Reach		(mitigation site feet)		par impact site foot	
IR vs MR1				0.78	
IR vs MR2				(see note 15) #DIV/0!	
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!
#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!	#DIV/0!

Instructions

1) Describe the project impacts:

- a) Indicate when the impact(s) will take place (i.e., Impact Year)
- b) Estimate the Ecological Integrity (EI) prior to project impacts (i.e., Pre-impact)
- c) Predict Ecological Integrity (EI) after the proposed impacts occur (i.e., Post-impact)
- d) Prescribe the length of stream reach represented by this proposed impact

2) Describe the proposed mitigation used to offset proposed impacts:

- a) Indicate when the proposed mitigation will take place (i.e., Year Started)
- b) Predict when the mitigation project will reach maturity (i.e., Year Matured)
- c) Estimate the Risk of Failure for the specific proposed mitigation site and plan
- d) Estimate the Ecological Integrity of the proposed mitigation site before any work is done (i.e., Pre-Work), immediately After Work, and At Maturity
- e) Indicate the linear distance of the proposed mitigation offered to offset proposed impacts
- f) If necessary, (indicated by a balance > 0 in Column P), continue with additional mitigation sites


User Notes:

- 1) User only needs to fill out the gray shaded boxes
- 2) Use a separate spreadsheet for each homogeneous impact reach to be mitigated

Macroinvertebrate
Data - Family Level
(Rifle Only)

11. Family Taxa Richness	0	# of taxa sampled
12. Family EPT Richness	0	# of EPT species sampled
13. % Ephemeroptera	0	% Mayflies (0-100)
14. % Chironomidae & Oligochaeta	0	% Midges & Worms (0-100)
16. mFBI	0	no units

Macroinvertebrate BIODIVERSITY	NA	MAIDIS	MAIDIS
conductivity	368		



Appendix H

EII Calculation Five Years after Restoration

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)**Stream/Reach:** HF-15**Assessment Objectives:** Immediately after restored

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.32	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables**Measure****Units***Enter quantitative or categorical measure from Field Data Sheet in shaded cells***RBP Habitat Parameters**

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	10	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	2	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	12	no units (0-20)
10. Riparian Width (both combined)	14	no units (0-20)

Total Habitat Score**142**

no units

Subindex**Habitat Integrity****0.53****Macroinvertebrate Data - Genus/species Level**

11. Genus/species Taxa Richness		# of taxa sampled
12. Genus/species EPT Richness		# of EPT species sampled
13. % Ephemeroptera		% Mayflies (0-100)
14. % Chironomidae & Oligochaeta		% Midge & Worms (0-100)
15. % Clingers		% Clingers (0-100)
16. mHBI		no units

Macroinvertebrate Bioassessment**NA**

no units

NA**Conductivity****500**

microMHOs

0.10

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: Pond-106

Assessment Objectives: Immediately after restored

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.38	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables

Measure

Units

Enter quantitative or categorical measure from Field Data Sheet in shaded cells

RBP Habitat Parameters

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	10	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	10	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	12	no units (0-20)
10. Riparian Width (both combined)	14	no units (0-20)

Total Habitat Score

150

no units

Subindex

Habitat Integrity

0.67

Macroinvertebrate Data - Genus/species Level

11. Genus/species Taxa Richness		# of taxa sampled
12. Genus/species EPT Richness		# of EPT species sampled
13. % Ephemeroptera		% Mayflies (0-100)
14. % Chironomidae & Oligochaeta		% Midges & Worms (0-100)
15. % Clingers		% Clingers (0-100)
16. mHBI		no units
Macroinvertebrate Bioassessment	NA	no units
Conductivity	500	microMHOs

NA

0.10

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: HF-16

Assessment Objectives: Immediately after restored

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.30	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables

Measure

Units

Enter quantitative or categorical measure from Field Data Sheet in shaded cells

RBP Habitat Parameters

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	9	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	1	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	12	no units (0-20)
10. Riparian Width (both combined)	14	no units (0-20)

Total Habitat Score

140

no units

Subindex

Habitat Integrity

0.50

Macroinvertebrate Data - Genus/species Level

11. Genus/species Taxa Richness		# of taxa sampled
12. Genus/species EPT Richness		# of EPT species sampled
13. % Ephemeroptera		% Mayflies (0-100)
14. % Chironomidae & Oligochaeta		% Midges & Worms (0-100)
15. % Clingers		% Clingers (0-100)
16. mHBI		no units
Macroinvertebrate Bioassessment	NA	no units
Conductivity	500	microMHOs

NA

0.10

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: Pond-107

Assessment Objectives: Immediately after restored

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.38	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables

Measure

Units

Enter quantitative or categorical measure from Field Data Sheet in shaded cells

RBP Habitat Parameters

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	10	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	9	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	12	no units (0-20)
10. Riparian Width (both combined)	14	no units (0-20)

Total Habitat Score

149

no units

Subindex

Habitat Integrity

0.65

Macroinvertebrate Data - Genus/species Level

11. Genus/species Taxa Richness		# of taxa sampled
12. Genus/species EPT Richness		# of EPT species sampled
13. % Ephemeroptera		% Mayflies (0-100)
14. % Chironomidae & Oligochaeta		% Midges & Worms (0-100)
15. % Clingers		% Clingers (0-100)
16. mHBI		no units

Macroinvertebrate Bioassessment

NA

no units

NA

Conductivity

500

microMHOs

0.10

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)**Stream/Reach:** HF-17**Assessment Objectives:** Immediately after restored

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.30	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables**Measure****Units***Enter quantitative or categorical measure from Field Data Sheet in shaded cells***RBP Habitat Parameters**

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	9	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	0	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	12	no units (0-20)
10. Riparian Width (both combined)	14	no units (0-20)

Total Habitat Score**139**

no units

Subindex**Habitat Integrity****0.49****Macroinvertebrate Data - Genus/species Level**

11. Genus/species Taxa Richness		# of taxa sampled
12. Genus/species EPT Richness		# of EPT species sampled
13. % Ephemeroptera		% Mayflies (0-100)
14. % Chironomidae & Oligochaeta		% Midges & Worms (0-100)
15. % Clingers		% Clingers (0-100)
16. mHBI		no units
Macroinvertebrate Bioassessment	NA	no units
Conductivity	500	microMHOs

NA**0.10**

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: Pond-92

Assessment Objectives: Immediately after restored

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.30	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables

Measure

Units

Enter quantitative or categorical measure from Field Data Sheet in shaded cells

RBP Habitat Parameters

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	9	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	0	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	12	no units (0-20)
10. Riparian Width (both combined)	14	no units (0-20)

Total Habitat Score

139

no units

Subindex

Habitat Integrity

0.49

Macroinvertebrate Data - Genus/species Level

11. Genus/species Taxa Richness		# of taxa sampled
12. Genus/species EPT Richness		# of EPT species sampled
13. % Ephemeroptera		% Mayflies (0-100)
14. % Chironomidae & Oligochaeta		% Midges & Worms (0-100)
15. % Clingers		% Clingers (0-100)
16. mHBI		no units
Macroinvertebrate Bioassessment	NA	no units
Conductivity	500	microMHOs

NA

0.10

Appendix I

EII Calculation for 30 Years after Disturbance

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)**Stream/Reach:** HF-15**Assessment Objectives:** 30 Years Post Disturbance

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.37	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables**Measure****Units***Enter quantitative or categorical measure from Field Data Sheet in shaded cells***RBP Habitat Parameters**

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	10	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	2	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	14	no units (0-20)
10. Riparian Width (both combined)	18	no units (0-20)

Total Habitat Score

148

no units

Subindex**Habitat Integrity**

0.63

Macroinvertebrate Data - Genus/species Level

11. Genus/species Taxa Richness		# of taxa sampled
12. Genus/species EPT Richness		# of EPT species sampled
13. % Ephemeroptera		% Mayflies (0-100)
14. % Chironomidae & Oligochaeta		% Midge & Worms (0-100)
15. % Clingers		% Clingers (0-100)
16. mHBI		no units
Macroinvertebrate Bioassessment	NA	no units
Conductivity	500	microMHOs

NA

0.10

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: Pond-106

Assessment Objectives: 30 Years Post Disturbance

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.43	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables

Measure

Units

Enter quantitative or categorical measure from Field Data Sheet in shaded cells

RBP Habitat Parameters

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	10	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	10	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	14	no units (0-20)
10. Riparian Width (both combined)	18	no units (0-20)

Total Habitat Score

156

no units

Subindex

Habitat Integrity

0.77

Macroinvertebrate Data - Genus/species Level

11. Genus/species Taxa Richness		# of taxa sampled
12. Genus/species EPT Richness		# of EPT species sampled
13. % Ephemeroptera		% Mayflies (0-100)
14. % Chironomidae & Oligochaeta		% Midges & Worms (0-100)
15. % Clingers		% Clingers (0-100)
16. mHBI		no units

Macroinvertebrate Bioassessment

NA

no units

NA

Conductivity

500

microMHOs

0.10

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: HF-16

Assessment Objectives: 30 Years Post Disturbance

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.35	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables

Measure

Units

Enter quantitative or categorical measure from Field Data Sheet in shaded cells

RBP Habitat Parameters

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	9	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	1	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	14	no units (0-20)
10. Riparian Width (both combined)	18	no units (0-20)

Total Habitat Score

146

no units

Subindex

Habitat Integrity

.60

Macroinvertebrate Data - Genus/species Level

11. Genus/species Taxa Richness		# of taxa sampled
12. Genus/species EPT Richness		# of EPT species sampled
13. % Ephemeroptera		% Mayflies (0-100)
14. % Chironomidae & Oligochaeta		% Midges & Worms (0-100)
15. % Clingers		% Clingers (0-100)
16. mHBI		no units
Macroinvertebrate Bioassessment	NA	no units
Conductivity	500	microMHOs

NA

0.10

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: Pond-107

Assessment Objectives: 30 Years Post Disturbance

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.43	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables

Measure

Units

Enter quantitative or categorical measure from Field Data Sheet in shaded cells

RBP Habitat Parameters

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	10	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	9	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	14	no units (0-20)
10. Riparian Width (both combined)	18	no units (0-20)

Total Habitat Score

155

no units

Subindex

Habitat Integrity

.75

Macroinvertebrate Data - Genus/species Level

11. Genus/species Taxa Richness	# of taxa sampled
12. Genus/species EPT Richness	# of EPT species sampled
13. % Ephemeroptera	% Mayflies (0-100)
14. % Chironomidae & Oligochaeta	% Midges & Worms (0-100)
15. % Clingers	% Clingers (0-100)
16. mHBI	no units

Macroinvertebrate Bioassessment Conductivity

NA

no units

NA

500

microMHOS

0.10

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)**Stream/Reach:** HF-17**Assessment Objectives:** 30 Years Post Disturbance

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.34	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables**Measure****Units***Enter quantitative or categorical measure from Field Data Sheet in shaded cells***RBP Habitat Parameters**

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	9	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	0	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	14	no units (0-20)
10. Riparian Width (both combined)	18	no units (0-20)

Total Habitat Score

145

no units

Subindex**Habitat Integrity**

0.58

Macroinvertebrate Data - Genus/species Level

11. Genus/species Taxa Richness		# of taxa sampled
12. Genus/species EPT Richness		# of EPT species sampled
13. % Ephemeroptera		% Mayflies (0-100)
14. % Chironomidae & Oligochaeta		% Midges & Worms (0-100)
15. % Clingers		% Clingers (0-100)
16. mHBI		no units

Macroinvertebrate Bioassessment

NA

no units

NA

Conductivity

500

microMHOs

0.10

Project ID: Nally & Hamilton (Permit No. 860-0380, Am #6)

Stream/Reach: Pond-92

Assessment Objectives: 30 Years Post Disturbance

NA	Ecological Integrity Index (MBI + Habitat Integrity + Conductivity)		
0.34	Ecological Integrity Index (Habitat Integrity + Conductivity)		

Variables

Measure

Units

Enter quantitative or categorical measure from Field Data Sheet in shaded cells

RBP Habitat Parameters

1. Epifaunal Substrate	17	no units (0-20)
2. Embeddedness	17	no units (0-20)
3. Velocity/Depth Regime	9	no units (0-20)
4. Sediment Deposition	17	no units (0-20)
5. Channel Flow Status	0	no units (0-20)
6. Channel Alteration	15	no units (0-20)
7. Freq. Of Riffles (bends)	20	no units (0-20)
8. Bank stability (both combined)	18	no units (0-20)
9. Veg. Protection (both combined)	14	no units (0-20)
10. Riparian Width (both combined)	18	no units (0-20)

Total Habitat Score

145

no units

Subindex

Habitat Integrity

0.58

Macroinvertebrate Data - Genus/species Level

11. Genus/species Taxa Richness		# of taxa sampled
12. Genus/species EPT Richness		# of EPT species sampled
13. % Ephemeroptera		% Mayflies (0-100)
14. % Chironomidae & Oligochaeta		% Midges & Worms (0-100)
15. % Clingers		% Clingers (0-100)
16. mHBI		no units

Macroinvertebrate Bioassessment

NA

no units





NA

Conductivity

500

microMHOs

0.10



J-Hook
-NTS-

APOGEE
ENVIRONMENTAL CONSULTANTS, INC.




P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2826
Email: joelbeverly@hotmail.com

NALLY & HAMILTON
ENTERPRISES, INC.

J-HOOK DIAGRAM
Attachment 1

SCALE:

11/15/05



Log Vane -NTS-

APOGEE
ENVIRONMENTAL CONSULTANTS, INC.


P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2828
Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
ENTERPRISES, INC.**




VANE DIAGRAM
Attachment 2

SCALE:

11/15/05



**Rock Vane
-NTS-**



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.


P.O. Box 338 Tel: (606) 633-7877
Ermine, KY 41815 Fax: (606) 632-2828
Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
ENTERPRISES, INC.**

VANE DIAGRAM
Attachment 3

SCALE:

11/15/05



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.

P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2628
Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
ENTERPRISES, INC.**

STEP POOL DIAGRAM
Attachment 4

SCALE:

11/15/05



Longitudinal Profile Data Sheet - POND 107-AS

Project # _____ Project Name 860-0380 North #5
 Stream/Drainage SUGAR BRANCH Date 11-10-05
 GPS: N 37° 14' 01.1" W 83° 01' 32.3"
 County KNOTT State KY Quad BLACKLEY

Point	Distance from Beg(ft)	Elevation (ft)	Stream Characteristic	Water depth (Tenths)	Bankfull (Tenths)
1	0	89.0	RIFPLE	DRY	
2	8.86	89.6	RIFPLE	↑	4
3	22.02	90.4	RIFPLE		
4	31.51	90.9	RIFPLE		
5	37.86	90.7	POOL		
6	43.96	91.6	POOL		6
7	48.58	91.8	POOL		
8	53.12	92.7	RIFPLE		
9	69.37	93.3	RIFPLE		
10	87.47	93.9	RIFPLE		
11	101.76	94.8	RIFPLE		
12	128.56	96.7	RIFPLE		
13	149.91	97.3	RIFPLE	↓	
14	159.17	98.3	RIFPLE	DRY	
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					



Longitudinal Profile Data Sheet HOLLOW FILL 16-A5

Project # _____ Project Name B60-0380 ADM #5

Stream/Drainage SUGAR BRANCH Date 11-10-05

GPS: N 37°14'01.1" W 83°01'32.3"

County KANDOT State KY Quad BLACKKEY

Point	Distance from Beg(ft)	Elevation (ft)	Stream Characteristic	Water depth (Tenths)	Bankfull (Tenths)
1	0	98.3	RIFLE	DRY	
2	20.68	99.2	RIFLE	↑	
3	43.00	100.1	POOL	↓	
4	62.64	101.4	POOL	↓	3
5	70.24	103.3	RIFLE	DRY	
6	93.16	104.8	POOL	2"	
7	97.74	104.1	RIFLE	DRY	
8	110.20	105.6	RIFLE	↑	
9	124.54	110.3	RIFLE	↓	
10	142.44	113.6	RIFLE	↓	
11	162.32	112.8	RIFLE	DRY	
12	178.04	120.0	RIFLE	SHEET FLOW	
13	192.90	124.3	POOL	3"	6
14	209.88	124.7	RIFLE	SHEET FLOW	
15	212.20	126.3	RIFLE	SHEET FLOW	
16	230.52	127.8	RIFLE	SHEET FLOW	
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					



Cross Section Data Sheet — POND 107-AS

Project # _____ Project Name 860-0380 Hom #5
 Stream/Drainage SUGAR BRANCH Date 11-10-05
 GPS: N 37°14'01.1" W 83°01'32.3"
 County KNOTT State KY Quad BLACKEY
 Feature Surveyed ☒ riffle ☐ pool

Point	Distance from LB (ft)	Elevation (ft)	Description
1	0	98.0	HILL
2	5.73	96.7	TOP OF BANK
3	6.92	94.7	CHANNEL
4	11.12	94.7	CHANNEL
5	12.38	95.2	BANKFUL
6	15.07	95.3	BOTTOM OF BANK
7	20.99	97.7	TOP OF BANK
8	31.43	98.3	HILL
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			



Cross Section Data Sheet - HOLLOW FILL 16-AS

Project # _____ Project Name 860-0380 ADM #5
 Stream/Drainage SUGAR BRANCH Date 11-10-05
 GPS: N 37°14'01.1" W 83°01'32.3"
 County KNOTT State KY Quad BLACKKEY
 Feature Surveyed ☒ riffle ☐ pool

Point	Distance from LB (ft)	Elevation (ft)	Description
1	0	112.4	HILL
2	8.39	106.1	BOTTOM BANK
3	10.54	106.1	TOP OF BANK
4	11.86	104.3	CHANNEL
5	17.72	103.4	THALWEG
6	19.75	103.8	CHANNEL
7	20.94	104.8	BANKFUL
8	22.97	106.2	TOP OF BANK
9	29.33	103.7	HILL
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			

02/28/2005 15:54 6066423258

CELRL DP CARR CREEK

PAGE 01

Stream Channel Classification (Level II) ...	
Stream NAME:	UNNAMED TRAIL TO BREWSTER CREEK
Basin NAME:	HOLLOW FALL 17-A6
Drainage AREA:	27.3 acre
Location:	
Twp:	Rge: Sect: Qtr: Lat: Long:
Observer:	Date: 1-11-06
Bankfull WIDTH (W_{bkf})	3.3 Feet
WIDTH of the stream channel, at bankfull stage elevation, in a riffle section.	
Mean DEPTH (d_{bkf})	0.25 Feet
Mean DEPTH of the stream channel cross-section, at bankfull stage elevation, in a riffle section.	
($d_{bkf} = A_{bkf} / W_{bkf}$)	
Bankfull Cross Section Area (A_{bkf})	0.159 Feet ²
AREA of the stream channel cross-section, at bankfull stage elevation, in a riffle section.	
WIDTH / DEPTH RATIO (W_{bkf} / d_{bkf})	13.2 F/Ft
Bankfull WIDTH divided by bankfull mean DEPTH, in a riffle section.	
Maximum DEPTH (d_{mbkf})	0.34 Feet
Maximum depth of the bankfull channel cross-section, or distance between the bankfull stage and thalweg elevations, in a riffle section.	
WIDTH of Flood-Prone Area (W_{fpa})	4.4 Feet
Twice maximum DEPTH, or ($2 \times d_{mbkf}$) = the stage/elevation at which flood-prone area WIDTH is determined in a riffle section.	
Entrenchment Ratio (ER)	1.33 F/Ft
The ratio of flood-prone area WIDTH divided by bankfull channel WIDTH (W_{fpa} / W_{bkf}) (riffle section)	
Channel Materials (Particle Size Index) D50	mm
The D50 particle size index represents the mean diameter of channel materials, as sampled from the channel surface, between the bankfull stage and thalweg elevations.	
Water Surface SLOPE (S)	26.6% F/Ft
Channel slope = "rise over run" for a reach approximately 20 - 30 bankfull channel widths in length, with the "riffle to riffle" water surface slope representing the gradient at bankfull stage.	
Channel SINUOSITY (K)	1.18
Sinuosity is an index of channel pattern, determined from a ratio of stream length divided by valley length (SL/VL); or estimated from a ratio of valley slope divided by channel slope (VS/S).	
Stream Type	For Reference, see page 5-4, 5-6: Rosgen, 1996. Applied River Morphology.



Pebble Count Data Sheet - Hollow FILL 17-86

Project # _____ Project Name NOH ADM 6

Stream/Drainage VANARCO TRLO BREEDING CK Date 1-11-06

GPS: N _____ W _____

County KUOFF State KY Quad _____

Point (m)	Pebble size (mm)	Point (m)	Pebble size (mm)	Point (m)	Pebble size (mm)	Point (m)	Pebble size (mm)
0	12	26	SAND	52		78	
1	25	27	9	53		79	
2	105	28	250	54		80	
3	44	29	30	55		81	
4	225	30	27	56		82	
5	134	31	255	57		83	
6	42 COAL	32	435	58		84	
7	32 COAL	33	95	59		85	
8	57	34	120	60		86	
9	10	35	28	61		87	
10	27	36	135	62		88	
11	66	37	14	63		89	
12	73	38	22	64		90	
13	55	39	186	65		91	
14	11	40	55	66		92	
15	27 COAL	41	77	67		93	
16	21	42	170	68		94	
17	75	43	160	69		95	
18	96	44	170	70		96	
19	17	45	19	71		97	
20	51	46	102	72		98	
21	16	47	56	73		99	
22	122	48	157	74		100	
23	66	49	170	75			
24	80	50	44	76			
25		51	83	77			



Longitudinal Profile Data Sheet

- Hollow FILL 17 AG

Project # 05-104.00 Project Name W4H PDM 6

Stream/Drainage UNNAMED TRAIL BREECHING CREEK Date 1-11-06

GPS: N 37°14'40.9" W 83°01'58.5"

County KNOTT State KY Quad Blackey

Point	Distance from Beg(ft)	Elevation (ft)	Stream Characteristic	Water depth (Tenths)	Bankfull (Tenths)
1	0	82.6	RIFFLE	DRY	
2	3.1	83.5	RIFFLE	↑	
3	17.7	85.4	RIFFLE		
4	22.8	87.4	RIFFLE		
5	29.5	88.4	RIFFLE		
6	31.0	88.7	POOL		3"
7	35.8	91.3	RIFFLE		
8	38.3	91.3	POOL		
9	42.4	93.8	RIFFLE		
10	64.3	97.5	RIFFLE		
11	71.0	100.2	RIFFLE		
12	83.8	102.0	RIFFLE		
13	97.2	105.4	RIFFLE		
14	102.1	106.1	RIFFLE		
15	104.1	107.0	RIFFLE		
16	105.6	107.1	POOL		
17	109.0	109.4	RIFFLE		
18	112.7	109.8	RIFFLE		
19	117.1	111.8	RIFFLE		
20	131.2	113.7	RIFFLE		
21	135.9	116.4	RIFFLE		
22	140.6	117.0	RIFFLE		
23	143.1	116.7	POOL	3	3"
24	145.3	118.3	RIFFLE		
25	157.5	120.5	RIFFLE		
26	159.6	120.3	POOL		
27	168.6	124.4	RIFFLE		
28	175.3	125.0	RIFFLE		
29	177.0	124.7	POOL	✓	
30	183.1	127.5	RIFFLE	DRY	



Hollow Fill 17-A6 cont...

Point	Distance from Beg(ft)	Elevation (ft)	Stream Characteristic	Water depth (Tenths)	Bankfull (Tenths)
31	214.3	135.2	R I F F L E	DRY	
32	227.8	132.4	R I F F L E	↑	
33	234.7	141.0	R I F F L E		
34	244.1	143.4	R I F F L E		
35	246.1	143.3	P o o l		
36	262.0	151.2	R I F F L E		
37	270.2	152.7	R I F F L E		
38	283.4	162.5	R I F F L E	V	
39	297.0	164.2	R I F F L E	DRY	
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					



Cross Section Data Sheet - HOLLOW FILL 17-A6

Project # 05-104.00 Project Name NOH ADM. 6
 Stream/Drainage UNNAMED TRAIL BREEDING CK Date 1-11-06
 GPS: N 37°14'40.9" W 83°01'58.5"
 County Kecoti State Ky Quad Blackey
 Feature Surveyed ☐ riffle ☒ pool

Point	Distance from LB (ft)	Elevation (ft)	Description
1	0	119.7	HILL
2	1.9	117.4	TOP OF BANK
3	3.4	117.0	BANK FUL
4	4.8	116.8	THALWEG
5	5.7	116.9	CHANNEL
6	7.4	119.2	TOP OF BANK
7	19.7	119.6	TOP OF BANK
8	24.1	117.0	THALWEG
9	29.1	120.7	HILL
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			



Cross Section Data Sheet - HOLLOW FILL 17 - A6

Project # 05-104.00 Project Name NH ADM 6
 Stream/Drainage UNNAMED TRAIL BECOMING CR Date 1-11-06
 GPS: N 37°14'40.9" W 83°01'58.5"
 County KNOTT State KY Quad Blackey
 Feature Surveyed ☒ riffle ☐ pool

Point	Distance from LB (ft)	Elevation (ft)	Description
1	0	109.0	HILL
2	5.2	106.7	BANKFUL
3	6.4	105.8	THALWEG
4	7.9	105.5	CHANNEL
5	9.8	105.8	TOP OF BANK
6	11.8	107.1	TOP OF BANK
7	21.9	107.3	CHANNEL
8	23.1	106.5	BOTTOM OF BANK / CHANNEL
9	25.8	107.0	TOP OF BANK
10	29.2	109.1	HILL
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			

02/28/2005 15:54

6056423258

CELRL OP CARR CREEK

PAGE 01


Stream Channel Classification (Level II) ...	
Stream NAME:	UNNAMED TRAIL TO DEFEATED CREEK
Basin NAME:	POND 22-A6
Drainage AREA:	51.6 acre mi ²
Location:	Kearney County
Twp:	Rge:
Sec:	Qtr:
Lat:	Long:
Observers:	Date:
Bankfull WIDTH (W_{bkt})	1.3 Feet
WIDTH of the stream channel, at bankfull stage elevation, in a riffle section.	
Mean DEPTH (d_{bkt})	0.25 Feet
Mean DEPTH of the stream channel cross-section, at bankfull stage elevation, in a riffle section.	
$(d_{bkt} = A_{bkt} / W_{bkt})$	
Bankfull Cross Section Area (A_{bkt})	2.98 Feet ²
AREA of the stream channel cross-section, at bankfull stage elevation, in a riffle section.	
WIDTH / DEPTH RATIO (W_{bkt} / d_{bkt})	5.2 F/Ft
Bankfull WIDTH divided by bankfull mean DEPTH, in a riffle section.	
Maximum DEPTH (d_{mbkt})	0.36 Feet
Maximum depth of the bankfull channel cross-section, or distance between the bankfull stage and thalweg elevations, in a riffle section.	
WIDTH of Flood-Prone Area (W_{fpa})	19.9 Feet
Twice maximum DEPTH, or $(2 \times d_{mbkt})$ = the stage/elevation at which flood-prone area WIDTH is determined in a riffle section.	
Entrenchment Ratio (ER)	15.31 F/Ft
The ratio of flood-prone area WIDTH divided by bankfull channel WIDTH (W_{fpa} / W_{bkt}) (riffle section)	
Channel Materials (Particle Size Index) D50	mm
The D50 particle size index represents the mean diameter of channel materials, as sampled from the channel surface, between the bankfull stage and thalweg elevations.	
Water Surface SLOPE (S)	26.7 F/Ft%
Channel slope = "rise over run" for a reach approximately 20 - 30 bankfull channel widths in length, with the "riffle to riffle" water surface slope representing the gradient at bankfull stage.	
Channel SINUOSITY (K)	1.12
Sinuosity is an index of channel pattern, determined from a ratio of stream length divided by valley length (SL/VL); or estimated from a ratio of valley slope divided by channel slope (VS/S).	
Stream Type	
For Reference, see page 5-5, 5-6; Rosgen, 1996. Applied River Morphology.	




Pebble Count Data Sheet

Project # _____ Project Name Lick Branch
 Stream/Drainage Lick Fork / Middle Fork KY Date _____
 GPS: N _____ W _____
 County Leslie State KY Quad Hoskinston

Point (m)	Pebble size (mm)		Point (m)	Pebble size (mm)		Point (m)	Pebble size (mm)		Point (m)	Pebble size (mm)	
0	5.14	R	30	sand	R	60	845	P	90	27	R
1	5.14	R	31	28	R	61	87	R	91	25	R
2	5.14	R	32	sand	R	62	133	P	92	sand	R
3	18	P	33	10	R	63	sand	P	93	300	R
4	20	P	34	68	R	64	35	R	94	80	P
5	6	P	35	10	R	65	9	R	95	37	P
6	sand	P	36	5	P	66	50	R	96	20	R
7	12	P	37	75	P	67	100	P	97	69	R
8	510	P	38	20	R	68	120	R	98	40	R
9	118	P	39	107	R	69	15	R	99	27	R
10	14	R	40	115	R	70	32	R	100	26	R
11	10	R	41	24	R	71	95	R	101		
12	sand	R	42	4	P	72	890	R	102		
13	40	R	43	45	R	73	120	R	103		
14	sand	R	44	27	R	74	32	R	104		
15	sand	R	45	23	R	75	90	R	105		
16	25	R	46	25	R	76	92	R	106		
17	7	P	47	70	R	77	50	R	107		
18	sand	P	48	sand	R	78	28	R	108		
19	sand	P	49	300	R	79	sand	P	109		
20	28	R	50	15	R	80	1200	R	110		
21	5	R	51	18	P	81	75	R	111		
22	44	R	52	82	P	82	72	R	112		
23	23	R	53	85	R	83	30	P	113		
24	18	R	54	120	R	84	120	R	114		
25	25	R	55	130	R	85	140	P	115		
26	26	R	56	20	R	86	sand	R	116		
27	35	R	57	65	P	87	38	R	117		
28	sand	R	58	18	R	88	25	R	118		
29	70	R	59	7	P	89	77	R	119		



Profile



Sinuosity

APOGEE
ENVIRONMENTAL CONSULTANTS, INC.



P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2628
Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
ENTERPRISES, INC.**

Typical longitudinal profile
of five to seven percent sloped stream,
Leslie County, Kentucky.

SCALE: 1"=50'

10/14/05



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.

P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2626
Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
ENTERPRISES, INC.**

Typical cross section
for five to seven percent grade stream,
Leslie County, Kentucky.

SCALE: 1"=5'

10/14/05

Appendix F

Stream Compensation Ratio Calculator Forms



Pebble Count Data Sheet – Hollow Fill 2

Project # 05.02 Project Name Carr Creek 404
 Stream/Drainage Unnamed Trib. To Carr Creek Date 10/6/03
 GPS: N 37d14'02.4" W 82d56'25.0"
 County Knott State KY Quad Blackey

Point (m)	Pebble size (mm)	Point (m)	Pebble size (mm)	Point (m)	Pebble size (mm)	Point (m)	Pebble size (mm)
0	Sand	26	138	52	111	78	17
1	13	27	8	53	11	79	55
2	87	28	245	54	16	80	Sand
3	90	29	378	55	13	81	Sand
4	161	30	34	56	3	82	100
5	103	31	490	57	12	83	8
6	Clay	32	60	58	Sand	84	195
7	285	33	Sand	59	325	85	75
8	53	34	Clay	60	15	86	41
9	290	35	Clay	61	31	87	55
10	36	36	3	62	355	88	Sand
11	58	37	37	63	23	89	13
12	15	38	1020	64	137	90	42
13	Sand	39	465	65	34	91	62
14	57	40	9	66	91	92	25
15	6	41	90	67	140	93	86
16	63	42	Sand	68	105	94	Sand
17	3	43	7	69	48	95	Sand
18	800	44	25	70	17	96	33
19	Sand	45	11	71	405	97	2
20	2	46	68	72	41	98	215
21	Sand	47	22	73	2	99	9
22	5	48	25	74	480	100	21
23	87	49	50	75	34		
24	105	50	125	76	46		
25	46	51	87	77	70		



Cross Section Data Sheet – Hollow Fill 2 22.9m

Project # 05.02 Project Name Carr Creek 404
 Stream/Drainage Unnamed Trib. To Carr Creek Date 10/8/03
 GPS: N 37d14'02.1" W 82d56'24.2"
 County Knott State KY Quad Blackey
 Feature Surveyed ☒ riffle ☐ pool


Point	Distance from L.B (ft)	Elevation (ft)	Description
1	0'0"	97.55	
2	6'3"	93.50	Top of Bank
3	6'7"	93.20	Bankfull
4	7'8"	92.55	Channel Dry
5	9'4"	92.35	Thalweg
6	12'4"	92.60	Channel Dry
7	14'1"	93.80	Top of Bank
8	16'10"	94.95	
9	26'8"	95.85	
10	32'8"	99.45	
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			




Cross Section Data Sheet – Hollow Fill 2 89.0m

Project # 05.02 Project Name Carr Creek 404
 Stream/Drainage Unnamed Trib. To Carr Creek Date 10/8/03
 GPS: N 37d14'00.5" W 82d56'23.1"
 County Knott State KY Quad Blackey
 Feature Surveyed ☒ riffle ☐ pool

Point	Distance from LB (ft)	Elevation (ft)	Description
1	0'0"	98.90	
2	4'2"	96.90	
3	6'9"	96.50	Top of Bank
4	8'4"	94.85	Bankfull
5	9'6"	94.17	Channel Dry
6	13'3"	94.37	
7	15'7"	93.86	Thalweg
8	18'7"	95.10	Channel Dry
9	21'3"	96.63	Top of Bank
10	27'9"	95.00	
11	32'0"	95.32	
12	35'6"	94.78	Top of Bank
13	38'1"	92.50	Bankfull
14	38'7"	92.05	Channel Dry
15	41'0"	90.20	Thalweg
16	42'11"	92.00	Channel Dry
17	44'3"	94.55	Top of Bank
18	47'0"	96.20	
19			
20			
21			
22			
23			
24			
25			



Cross Section Hollowfill 2 22.9m


Apogee
 ENVIRONMENTAL CONSULTANTS, LLC

P.O. Box 338 Tel: (606) 633-7677
 Ermine, KY 41815 Fax: (606) 632-2626
 Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
ENTERPRISES, INC.**

*Riffle Cross Section
 at Unnamed Trib. to Carr Creek Lake
 Knott County, Kentucky*

SCALE: 1"=4'


6/21/04




Cross Section Data Sheet – Hollow Fill 2 46.0m

Project # 05.02 Project Name Carr Creek 404
 Stream/Drainage Unnamed Trib. To Carr Creek Date 10/8/03
 GPS: N 37d14'01.6" W 82d56'23.6"
 County Knott State KY Quad Blackey
 Feature Surveyed ☐ riffle ☒ pool

Point	Distance from LB (ft)	Elevation (ft)	Description
1	0'0"	99.62	
2	6'8"	95.18	Small Channel Dry
3	10'5"	94.55	Thalweg
4	12'6"	95.46	Top of Bank
5	16'10"	95.51	
6	20'3"	94.61	
7	28'8"	93.95	Top of Bank
8	31'8"	90.02	Thalweg
9	33'6"	90.07	Middle Channel
10	36'3"	90.80	Channel Dry
11	37'0"	91.46	Bankfull
12	39'0"	95.30	Top of Bank
13	44'0"	98.00	
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			




Apogee
 ENVIRONMENTAL CONSULTANTS, LLC

P.O. Box 338 Tel: (606) 633-7677
 Ermine, KY 41815 Fax: (606) 632-2626
 Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
ENTERPRISES, INC.**

*Riffle Cross Section
 at Unnamed Trib. to Carr Creek Lake
 Knott County, Kentucky*

SCALE: 1"=5'


6/21/04




Cross Section Data Sheet – Hollow Fill 2 151.8m

Project # 05.02 Project Name Carr Creek 404
 Stream/Drainage Unnamed Trib. To Carr Creek Date 10/8/03
 GPS: N 37d13'59.4" W 82d56'21.2"
 County Knott State KY Quad Blackey
 Feature Surveyed ☐ riffle ☒ pool

Point	Distance from LB (ft)	Elevation (ft)	Description
1	0'9"	100.00	
2	1'2"	97.10	
3	6'10"	91.90	Top of Bank
4	7'11"	91.10	Bankfull
5	9'5"	89.95	Edge of Water
6	10'6"	89.77	Thalweg
7	11'7"	90.20	Edge of Water
8	12'9"	90.11	Channel
9	20'9"	98.00	Top of Bank
10	27'8"	97.70	
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			



Cross Section Hollowfill 2 151.8m


Apogee
 ENVIRONMENTAL CONSULTANTS, LLC

P.O. Box 338 Tel: (606) 633-7877
 Ermine, KY 41815 Fax: (606) 632-2626
 Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
ENTERPRISES, INC.**


*Pool Cross Section
 at Unnamed Trib. to Carr Creek Lake
 Knott County, Kentucky*

SCALE: 1"=4'


6/21/04

Appendix D

Longitudinal Profile, Cross Sections, and Pebble Counts for Streams to be Disturbed at Proposed Project Area



Profile



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.

P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2626
Email: joelbeverly@hotmail.com



**NALLY & HAMILTON
ENTERPRISES, INC.**

Longitudinal Profile
of Pond 107-A5
Knott County, Kentucky.

SCALE:

1"=30'

11/15/05



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.

P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2626
Email: joelbeverly@hotmail.com



**NALLY & HAMILTON
ENTERPRISES, INC.**

Longitudinal Profile
of Hollow Fill 16-A5
Knott County, Kentucky.

SCALE:

1"=30'

11/15/05



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.



P.O. Box 338 Tel: (606) 633-7877
Ermins, KY 41815 Fax: (606) 632-2826
Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
ENTERPRISES, INC.**

Longitudinal Profile
of Pond 106-A5
Knott County, Kentucky.

SCALE: 1"=30'

11/15/05



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.

P.O. Box 338 Tel: (606) 633-7877
Ermine, KY 41815 Fax: (606) 632-2626
Email: joelbeverly@hotmail.com


**NALLY & HAMILTON
ENTERPRISES, INC.**


Longitudinal Profile
of Hollow Fill 15-A5
Knott County, Kentucky.

SCALE:


1"=30'

11/15/05






Profile



Sinosity



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.

P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2828
Email: joelbeverly@hotmail.com


**NALLY & HAMILTON
ENTERPRISES, INC.**

Longitudinal Profile
of Hollow Fill 17-A6
Knott County, Kentucky.

SCALE:

1"=40'

1/11/06



Typical Section Hollow Fill 15-A5



P.O. Box 338 Tel: (806) 633-7677
 Ermine, KY 41815 Fax: (806) 632-2626
 Email: joelbeverly@hotmail.com


**NALLY & HAMILTON
 ENTERPRISES, INC.**

Cross Section

SCALE:

1"=5'

11/15/05



P.O. Box 338 Tel: (606) 633-7677
 Ermine, KY 41815 Fax: (606) 832-2626
 Email: joelbeverly@hotmail.com


**NALLY & HAMILTON
 ENTERPRISES, INC.**

Cross Section

SCALE:

1"=15'

1/11/06



Typical Section Hollow Fill 16-A5



P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2626
Email: joelbeverly@hotmail.com


**NALLY & HAMILTON
ENTERPRISES, INC.**

Cross Section

SCALE:

1"=5'

11/15/05



Typical Section Pond 107-A5



P.O. Box 338 Tel: (606) 633-7677
 Ermine, KY 41815 Fax: (606) 632-2828
 Email: joelbeverly@hotmail.com


**NALLY & HAMILTON
 ENTERPRISES, INC.**

Cross Section

SCALE:

1"=5'

11/15/05



P.O. Box 338 Tel: (606) 633-7677
 Ermine, KY 41815 Fax: (606) 632-2626
 Email: joelbeverly@hotmail.com


**NALLY & HAMILTON
 ENTERPRISES, INC.**

Cross Section


SCALE:

1"=15'

1/11/06



Typical Section Hollow Fill 17-A6 Riffle



Typical Section Hollow Fill 17-A6 Pool



P.O. Box 338 Tel: (606) 633-7677
Ermine, KY 41815 Fax: (606) 632-2626
Email: joelbeverly@hotmail.com


**NALLY & HAMILTON
ENTERPRISES, INC.**

Cross Section

SCALE:

1"=5'

1/11/06



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.

P.O. Box 398 Tel: (808) 633-7877
Ermina, KY 41815 Fax: (808) 632-2628
Email: joelbeverly@hotmail.com


**NALLY & HAMILTON
ENTERPRISES**

Attachment 5. Longitudinal Profile
of Pond 92-A6
Knott County, Kentucky.

SCALE:

1"=40'

1/11/06



APOGEE
ENVIRONMENTAL CONSULTANTS, INC.

P.O. Box 338 Tel: (808) 833-7677
Ermine, KY 41815 Fax: (808) 832-2828
Email: joelbeverly@hotmail.com

**NALLY & HAMILTON
ENTERPRISES**

Cross Section
Amendment 5

SCALE:

1"=15'

1/11/06

02/28/2005 15:54

6066423258

CELRL OP CARR CREEK

PAGE 81

Stream Channel Classification (Level II) _____	
Stream NAME:	UNNAMED TRIB TO DEFEATED CREEK
Basin NAME:	HF 15-AS
Drainage AREA:	50.6 acre mi^2
Location:	CARR FORK LAKE
Twp:	Rge:
Sec:	Qtr:
Lat:	Long:
Observers:	Date: 11-10-05
Bankfull WIDTH (W_{bkf}) 5.92 Feet WIDTH of the stream channel, at bankfull stage elevation, in a riffle section.	
Mean DEPTH (d_{bkf}) 0.68 Feet Mean DEPTH of the stream channel cross-section, at bankfull stage elevation, in a riffle section. ($d_{bkf} = A_{bkf} / W_{bkf}$)	
Bankfull Cross Section Area (A_{bkf}) 12.29 Feet² AREA of the stream channel cross-section, at bankfull stage elevation, in a riffle section.	
WIDTH / DEPTH RATIO (W_{bkf} / d_{bkf}) 8.71 FWT Bankfull WIDTH divided by bankfull mean DEPTH, in a riffle section.	
Maximum DEPTH (d_{mbk}) 1.09 Feet Maximum depth of the bankfull channel cross-section, or distance between the bankfull stage and thalweg elevations, in a riffle section.	
WIDTH of Flood-Prone Area (W_{fpa}) 10.5 Feet Twice maximum DEPTH, or ($2 \times d_{mbk}$) = the stage/elevation at which flood-prone area WIDTH is determined in a riffle section.	
Entrenchment Ratio (ER) 1.77 FWT The ratio of flood-prone area WIDTH divided by bankfull channel WIDTH (W_{fpa} / W_{bkf}) (riffle section)	
Channel Materials (Particle Size Index) D50 _____ mm The D50 particle size index represents the mean diameter of channel materials, as sampled from the channel surface, between the bankfull stage and thalweg elevations.	
Water Surface SLOPE (S) 20.5 FWT% Channel slope = "rise over run" for a reach approximately 20 - 30 bankfull channel widths in length, with the "riffle to riffle" water surface slope representing the gradient at bankfull stage.	
Channel SINUOSITY (K) 1.12 Sinuosity is an index of channel pattern, determined from a ratio of stream length divided by valley length (SL/VL); or estimated from a ratio of valley slope divided by channel slope (VS/S).	
Stream Type _____	

For Reference, see page 5-6, 5-8:
 Roegner, 1990. Applied River Morphology.



Pebble Count Data Sheet

Project # _____ Project Name 860-0380 AOM HS
 Stream/Drainage UNNAMED TALE DEFERRED CK Date 11-10-05
 GPS: N 37°13'50.7" W 83°01'58.1"
 County KNOX State KY Quad BLACKLEY

Point (m)	Pebble size (mm)	Point (m)	Pebble size (mm)	Point (m)	Pebble size (mm)	Point (m)	Pebble size (mm)
0	152	26	12	52		78	
1	42	27	76	53		79	
2	5	28	22	54		80	
3	204	29	1700	55		81	
4	444	30	326	56		82	
5	213	31	178	57		83	
6	32	32	35	58		84	
7	1	33	890	59		85	
8	52LT	34	14	60		86	
9	45	35	52LT	61		87	
10	293	36	213	62		88	
11	11	37	66	63		89	
12	445	38	17	64		90	
13	32	39	86	65		91	
14	24	40	46	66		92	
15	3	41	525	67		93	
16	102	42	52LT	68		94	
17	34	43	634	69		95	
18	66	44	78	70		96	
19	78	45	1100	71		97	
20	40	46	98	72		98	
21	489	47	163	73		99	
22	172	48	95	74		100	
23	3000ER	49	794	75			
24	28	50	32	76			
25	5400	51		77			



Longitudinal Profile Data Sheet - HOLLOW FILL 15-AS

Project # _____ Project Name 860-0380 ADM #5

Stream/Drainage UNNAMED TRIB DEFEATED CK Date 11-10-05

GPS: N 37° 13' 50.7" W 83° 01' 58.1"

County KNOTT State KY Quad BLACKLEY

Point	Distance from Beg(ft)	Elevation (ft)	Stream Characteristic	Water depth (Tenths)	Bankfull (Tenths)
1	0	72.0	RIFLE	DRY	
2	9.7	72.0	POOL	↑	
3	15.1	73.9	RIFLE	↓	
4	26.6	76.9	RIFLE	DRY	5
5	35.4	78.0	POOL	4"	
6	43.7	80.6	RIFLE	DRY	
7	53.5	82.0	POOL	2"	
8	63.9	85.1	RIFLE	DRY	
9	72.2	87.9	RIFLE	↑	
10	75.6	88.3	POOL		
11	83.0	93.8	RIFLE		6
12	92.5	94.2	RIFLE		
13	100.0	97.3	RIFLE		
14	115.1	97.3	POOL		
15	127.5	99.1	RIFLE		
16	138.9	100.9	RIFLE		
17	142.6	101.3	POOL		
18	153.0	102.9	RIFLE		
19	154.4	103.2	POOL		
20	175.7	104.5	RIFLE		
21	182.0	106.3	RIFLE	↓	
22	191.7	109.8	POOL	DRY	6
23					
24					
25					
26					
27					
28					
29					
30					



Cross Section Data Sheet - HOLLOW FILL 15-AS

Project # _____ Project Name 860-0380 AOM #5
 Stream/Drainage UNNAMED REG OFFFATED PK Date 11-10-05
 GPS: N 37°13'50.7" W 83°01'58.1"
 County KNOTT State KY Quad BLALKEY
 Feature Surveyed ☒ riffle ☐ pool

Point	Distance from LB (ft)	Elevation (ft)	Description
1	0	104.2	HILL
2	10.25	100.5	BOTTOM OF BANK
3	12.46	100.2	TOP OF BANK
4	21.28	98.5	BANKFUL CHANNEL
5	23.22	97.4	CHANNEL
6	26.11	98.1	CHANNEL
7	30.24	99.7	TOP OF BANK
8	41.70	103.1	HILL
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			

02/28/2005 15:54

5066423258

CELRL OP CARR CREEK

PAGE 01

Stream Channel Classification (Level II) —	
Stream NAME: <u>SUGAR BRANCH</u>	
Basin NAME: <u>HF 16-A5</u>	Drainage AREA: <u>56.5</u> acre <u> </u> mi ²
Location: <u>CARR FORK LAKE</u>	
Twp: <u> </u>	Rge: <u> </u> Sec: <u> </u> Qtr: <u> </u> Lat: <u> </u> Long: <u> </u>
Observer: <u> </u>	Date: <u>11-10-05</u>
Bankfull WIDTH (W_{bkf}) <u>8.44</u> Feet	
WIDTH of the stream channel, at bankfull stage elevation, in a riffle section.	
Mean DEPTH (d_{bkf}) <u>0.55</u> Feet	
Mean DEPTH of the stream channel cross-section, at bankfull stage elevation, in a riffle section. ($d_{bkf} = A_{bkf} / W_{bkf}$)	
Bankfull Cross Section Area (A_{bkf}) <u>4.2</u> Feet ²	
AREA of the stream channel cross-section, at bankfull stage elevation, in a riffle section.	
WIDTH / DEPTH RATIO (W_{bkf} / d_{bkf}) <u>15.35</u> F/FT	
Bankfull WIDTH divided by bankfull mean DEPTH, in a riffle section.	
Maximum DEPTH (d_{mbkf}) <u>0.9</u> Feet	
Maximum depth of the bankfull channel cross-section, or distance between the bankfull stage and thalweg elevations, in a riffle section.	
WIDTH of Flood-Prone Area (W_{fpa}) <u>10.4</u> Feet	
Twice maximum DEPTH, or ($2 \times d_{mbkf}$) = the stage/elevation at which flood-prone area WIDTH is determined in a riffle section.	
Entrenchment Ratio (ER) <u>1.23</u> F/FT	
The ratio of flood-prone area WIDTH divided by bankfull channel WIDTH (W_{fpa} / W_{bkf}) (riffle section)	
Channel Materials (Particle Size Index) D50 <u> </u> mm	
The D50 particle size index represents the mean diameter of channel materials, as sampled from the channel surface, between the bankfull stage and thalweg elevations.	
Water Surface SLOPE (S) <u>18.9</u> F/FT%	
Channel slope = "rise over run" for a reach approximately 20 - 30 bankfull channel widths in length, with the "riffle to riffle" water surface slope representing the gradient at bankfull stage.	
Channel SINUOSITY (K) <u>1.04</u>	
Sinuosity is an index of channel pattern, determined from a ratio of stream length divided by valley length (SL/VL); or estimated from a ratio of valley slope divided by channel slope (VS/S).	
Stream Type <u> </u>	
For Reference, see page 5-6, 6-6: Roegen, 1998. Applied River Morphology.	

82/28/2805 15:54

6866423258

CELRL OF CARR CREEK

PAGE 01

Stream Channel Classification (Level II) —

Stream NAME: SUGAR BRANCH
 Basin NAME: POND 107-AS Drainage AREA: 70.9 acre mi²
 Location: CARR CREEK
 Twp: _____ Rge: _____ Sec: _____ Qtr: _____ Lat: _____ Long: _____
 Observer: _____ Date: 11-10-05

Bankfull WIDTH (W_{bkt})5.74 Feet

WIDTH of the stream channel, at bankfull stage elevation, in a riffle section.

Mean DEPTH (d_{bkt})0.39 FeetMean DEPTH of the stream channel cross-section, at bankfull stage elevation, in a riffle section.
($d_{bkt} = A_{bkt} / W_{bkt}$)Bankfull Cross Section Area (A_{bkt})2.48 Feet²

AREA of the stream channel cross-section, at bankfull stage elevation, in a riffle section.

WIDTH / DEPTH RATIO (W_{bkt} / d_{bkt})14.72 FVFT

Bankfull WIDTH divided by bankfull mean DEPTH, in a riffle section.

Maximum DEPTH (d_{mbkt})0.52 Feet

Maximum depth of the bankfull channel cross-section, or distance between the bankfull stage and thalweg elevations, in a riffle section.

WIDTH of Flood-Prone Area (W_{fpa})9.74 FeetTwice maximum DEPTH, or ($2 \times d_{mbkt}$) = the stage/elevation at which flood-prone area WIDTH is determined in a riffle section.

Entrenchment Ratio (ER)

1.69 FVFTThe ratio of flood-prone area WIDTH divided by bankfull channel WIDTH (W_{fpa} / W_{bkt}) (riffle section)

Channel Materials (Particle Size Index) D50

_____ mm

The D50 particle size index represents the mean diameter of channel materials, as sampled from the channel surface, between the bankfull stage and thalweg elevations.

Water Surface SLOPE (S)

4.0 FVFT%

Channel slope = "rise over run" for a reach approximately 20 - 30 bankfull channel widths in length, with the "riffle to riffle" water surface slope representing the gradient at bankfull stage.

Channel SINUOSITY (K)

1.34Sinuosity is an index of channel pattern, determined from a ratio of stream length divided by valley length (SL/VL); or estimated from a ratio of valley slope divided by channel slope (VS/S).

Stream Type

For Reference, see page 5-6, 6-6:
Rosen, 1990, Applied River Morphology.